

62763

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 STATE	Y025 (PARKING) VILLAGE OF RIVER FOREST		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	4	1		
40600300	AGGREGATE (PRIME COAT)	TON	24	19	5		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	1	1		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	137	137			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	381	381			
44000115	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	1703	1703			
4400116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD	1701	1701			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	500	500			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	125	125			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1000	1000			
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	28	28			
60404940	FRAMES AND GRATES, TYPE 23	EACH	2	2			
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5			
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3260	3260			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	293	293			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	130	130			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7608	7608			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	164	164			

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 STATE	Y025 (PARKING) VILLAGE OF RIVER FOREST		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	51	51			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	147	147			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	363	363			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	293	293			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7608	7608			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	164	164			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	130	130			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	51	51			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	147	147			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	139	139			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	154	154			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	324	324			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	45	45			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6	6			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	976	786	190		
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	488	393	95		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	11617	9352	2265		
XX003560	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1100	1100			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			

* SPECIALTY ITEMS

Rev. 6-7-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
THATCHER AVENUE
CHICAGO AVENUE TO DIVISION STREET

PLOT DATE: 4/7/2005