

CONTRACT 62782

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE URBAN 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	258	258					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					
40600300	AGGREGATE (PRIME COAT)	TON	75	75					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3.8	3.8					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	28	28					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	1668	1668					
44000104	BITUMINOUS REMOVAL OVER PATCHES 1"	SQ YD	3722	3722					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	744	744					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	1489	1489					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1489	1489					
48101200 63100167	AGGREGATE SHOULDERS, TYPE B TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TON EACH	1427 9	1427 9					
63200310	GUARDRAIL REMOVAL	FOOT	450	450					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4000	4000					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37900	37900					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37900	37900					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	322	322					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	9	9					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	645	645					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	3200	3200					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1600	1600					
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	37237	37237					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
ILL 47

Rev.

PLOT DATE: 4/15/2005