

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-0561	COOK	47	7
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	62795	

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	
				1000 URBAN	100%STATE ^A
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,091	1,091	
25200110	SODDING, SALT TOLERANT	SQ YD	1,091	1,091	
30103000	SHAPING AND GRADING ROADWAY	UNIT	83	83	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	516	516	
42001300	PROTECTIVE COAT	SQ YD	5,938	5,938	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	399	399	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	48,563	48,563	
44201771	CLASS D PATCHES, TYPE IV, 10"	SQ YD	30	30	
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	10	10	
* 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	53	53	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	113	113	
60600605	CONCRETE CURB, TYPE B	FOOT	237	237	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	234	234	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26	
X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	324	324	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0076600	TRAINEES	HOUR			
XX001109	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"	SQ YD	117	117	
XX152400	SAND CUSHION, 3-INCH	CU YD	450	450	



0488
*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (WELLS ST SIDEWALKS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: LC
DATE: MARCH 4, 2005 CHECKED BY: JAL

03/02/2005 03:34:52 PM