

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-0571	COOK	47	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

62796

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	
				J000 URBAN	
				100% STATE	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,675	1,675	
25200110	SODDING, SALT TOLERANT	SQ YD	1,675	1,675	
30103000	SHAPING AND GRADING ROADWAY	UNIT	80	80	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	460	460	
42001300	PROTECTIVE COAT	SQ YD	5,543	5,543	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	275	275	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	45,501	45,501	
56109210	WATER VALVES TO BE ADJUSTED	EACH	10	10	
* 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	22	22	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	45	45	
60600605	CONCRETE CURB, TYPE B	FOOT	80	80	
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	86	86	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
* 81000300	CONDUIT IN TRENCH, 1" DIAMETER GALVANIZED STEEL	FOOT	5	5	
* 81000800	CONDUIT IN TRENCH, 3" DIAMETER GALVANIZED STEEL	FOOT	15	15	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3	3	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26	
X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	235	235	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOOR</del>			
XX001109	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"	SQ YD	185	185	
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	39	39	
XX152400	SAND CUSHION, 3-INCH	CU YD	431	431	

07880  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
59th ST TO 47th ST (WENTWORTH AVE SIDEWALKS)

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: MARCH 4, 2005

DRAWN BY: LC  
CHECKED BY: JAL