F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-094 I	COOK	40	5
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62835

SUMMARY OF QUANTITIES

URBAN
100% STATE

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY 1000
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	810	810
25200110	SODDING, SALT TOLERANT	SQ YD	810	810
30103000	SHAPING AND GRADING ROADWAY	UNIT	61	61
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	639	639
42001300	PROTECTIVE COAT	SQ YD	4,493	4,493
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	500	500
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	34,538	34,538
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	3	3
* 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	10	10
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	36	36
60600605	CONCRETE CURB, TYPE B	FOOT	151	151
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	469	469
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	3	3
XX001109	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"	SQ YD	139	139
XX152400	SAND CUSHION, 3 INCH	CU YD	320	320
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~		

~~Z0080~~
*SPECIALTY ITEMS

Rev. 5-26-05

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (SIDEWALKS & DRIVEWAYS)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: MARCH 04, 2005
DRAWN BY: JB
CHECKED BY: RMG

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5712, PHONE: (312) 938-0300

N:\04046\Civil\Plans\Contract\90-94 Dan Ryan\2004-094-I\Sheet 5 Summary of Quantities.dgn 03/07/2005 10:46:19 AM