

SUMMARY OF QUANTITIES

URBAN
100% STATE
ROADWAY

CODE NO.	ITEM	UNIT	QUANTITY	SFTY-ID
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7,086	7,086
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	603	603
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,992	7,992
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,513	3,513
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	775	775
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	504	504
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	521	521
78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SQ FT	603	603
78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	7,992	7,992
78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	3,513	3,513
78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	775	775
78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	504	504
78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	521	521
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0078600	TRAINEES	— HOUR —		

⊖Y080

PAVEMENT MARKING SCHEDULE

STATION TO STATION	SHEET	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"
		SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
WENTWORTH AVENUE							
99+99.22 TO 108+00.00	1	39	1,466	481	2	70	91
108+00.00 TO 122+00.00	2	-	410	178	142	53	35
122+00.00 TO 131+41.87	3	99	1,506	551	219	154	119
SUB-TOTALS		138	3,382	1,210	363	277	245
WELLS STREET							
506+92.81 TO 511+50.00	1	87	1,234	437	156	78	106
511+50.00 TO 525+50.00	2	-	362	233	-	-	41
525+50.00 TO 534+81.50	3	39	1,232	695	256	149	129
SUB-TOTALS		126	2,828	1,365	412	227	276
63RD STREET BRIDGE	1	184	905	360	-	-	-
59TH STREET BRIDGE	3	155	877	578	-	-	-
TOTALS		603	7,992	3,513	775	504	521


REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (PAVEMENT MARKINGS)

SUMMARY OF QUANTITIES
SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: March 4, 2005
DRAWN BY: NJH
CHECKED BY: RMG

Rev. 5-26-05



3/3/2005 10:57:08 AM