

FAY RTE 80/94	SECTION 0203.1B	COUNTY COOK	TOTAL SHEETS 200	SHEET NO. 5
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

NHI 90% FED. 10% STATE	NHP 80% FED. 20% STATE	NHI 90% FED./10% STATE
ROADWAY FAY-80	ROADWAY FAY-80 (IL 394)	SN 016-280A
		LIGHTING

CODE	PAY ITEM	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE			
				J000-2A	J000-2A	X971-2A	Y030-1E
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	77		77		
M2810107	STONE RIPRAP, CLASS A4	SQ M	83	83			
M2820200	FILTER FABRIC	SQ M	83	83			
M3111300	SUB-BASE GRANULAR MATERIAL, TYPE B 300MM	SQ M	550	550			
M3120100	STABILIZED SUB-BASE 100MM	SQ M	1698	1698			
M3120150	STABILIZED SUB-BASE 150MM	SQ M	550	550			
M4202285	PORTLAND CEMENT CONCRETE PAVEMENT 280MM (JOINTED)	SQ M	881	881			
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	85	85			
M4218000	PROTECTIVE COAT	SQ M	1158	1158			
M4402000	PAVEMENT REMOVAL	SQ M	127		127		
M4402530	PAVED SHOULDER REMOVAL	SQ M	111		111		
M4402540	PAVEMENT BREAKING	SQ M	839		839		
M4812280	AGGREGATE SHOULDERS, TYPE B 280MM	SQ M	62	62			
M4830150	PORTLAND CEMENT CONCRETE SHOULDERS - 150MM	SQ M	88	88			
M4830280	PORTLAND CEMENT CONCRETE SHOULDERS - 280MM	SQ M	718	718			
M4830360	PORTLAND CEMENT CONCRETE SHOULDERS - 360MM	SQ M	529	529			
M4832000	PROTECTIVE COAT	SQ M	1335	1335			
M5020100	STRUCTURE EXCAVATION	CU M	1473			1473	
M5030105	NEOPRENE EXPANSION JOINT 50MM	METER	9.5			9.5	
M5030350	CONCRETE STRUCTURES	CU M	1148.3			1148.3	
M5030360	CONCRETE SUPERSTRUCTURE	CU M	1585.5			1585.5	
M5030390	BRIDGE DECK GROOVING	SQ M	5036			5036	
M5030450	PROTECTIVE COAT	SQ M	6459.4			6459.4	
M5050305	ERECTING STRUCTURAL STEEL	L SUM	1			1	
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	1170			1170	
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	365940			365940	
M5110100	SLOPE WALL 100 MM	SQ M	324			324	
M5120160	FURNISHING STEEL PILES HP310X79	METER	990			990	
M5120180	FURNISHING STEEL PILES HP360X108	METER	3596.2			3596.2	
M5120315	DRIVING STEEL PILES	METER	4586.2			4586.2	
M5120460	TEST PILE STEEL HP310X79	EACH	2			2	
M5120480	TEST PILE STEEL HP360X108	EACH	8			8	
M5120900	TEMPORARY SHEET PILING	SQ M	43.2			43.2	

- * SPECIALTY ITEM
- ** SFTY-3N
- △ Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94 WB FLYOVER RAMP
TO SB IL 394 (RAMP G)

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: MARCH 23, 2005
DRAWN BY: BJM
CHECKED BY: JES

