

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET No. 12 91 SHEETS
F. A. I. 80/94	0203.1B	COOK	200	74	
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT-	CONTRACT NO. 62854		

GIRDER 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. E. Abut	120+323.500	6.30	191.918	191.918
CL Brg. E. Abut	120+324.550	6.30	191.967	191.967
A	120+327.550	6.30	192.110	192.115
B	120+330.550	6.30	192.252	192.262
C	120+333.550	6.30	192.394	192.407
D	120+336.550	6.30	192.537	192.553
E	120+339.550	6.30	192.679	192.696
F	120+342.550	6.30	192.821	192.837
G	120+345.543	6.30	192.963	192.977
H	120+348.482	6.30	193.103	193.115
I	120+351.420	6.30	193.242	193.250
J	120+354.359	6.30	193.381	193.385
K	120+357.298	6.30	193.521	193.521
L	120+360.236	6.30	193.660	193.657
M	120+363.175	6.30	193.800	193.795
N	120+366.114	6.30	193.931	193.925
O	120+369.053	6.30	194.048	194.044
CL Pier 1	120+372.200	6.30	194.174	194.174
P	120+375.139	6.30	194.292	194.300
Q	120+378.077	6.30	194.409	194.427
R	120+381.016	6.30	194.527	194.557
S	120+383.955	6.30	194.644	194.686
T	120+386.893	6.30	194.762	194.817
U	120+389.832	6.30	194.879	194.948
V	120+392.771	6.30	194.997	195.077
W	120+395.710	6.30	195.114	195.205
X	120+398.648	6.30	195.232	195.331
Y	120+401.587	6.30	195.349	195.454
Z	120+404.526	6.30	195.467	195.574
AA	120+407.464	6.30	195.584	195.691
AB	120+410.403	6.30	195.700	195.803
AC	120+413.342	6.30	195.815	195.913
AD	120+416.280	6.30	195.928	196.018
AE	120+419.219	6.30	196.041	196.120
AF	120+422.158	6.30	196.152	196.219
AG	120+425.097	6.30	196.261	196.316
AH	120+428.035	6.30	196.370	196.412
AI	120+430.974	6.30	196.477	196.507
AJ	120+433.913	6.30	196.584	196.604
AK	120+436.851	6.30	196.689	196.701
AL	120+439.790	6.30	196.792	196.797
AM	120+442.729	6.30	196.895	196.896
CL Pier 2	120+445.600	6.30	196.994	196.994
AN	120+448.539	6.30	197.094	197.097
AO	120+451.477	6.30	197.193	197.202
AP	120+454.416	6.30	197.291	197.308
AQ	120+457.355	6.30	197.387	197.414
AR	120+460.293	6.30	197.482	197.520
AS	120+463.232	6.30	197.576	197.626
AT	120+466.171	6.30	197.669	197.732
AU	120+469.110	6.30	197.761	197.836
AV	120+472.048	6.30	197.851	197.936
AW	120+474.987	6.30	197.940	198.034
AX	120+477.926	6.30	198.028	198.129
AY	120+480.864	6.30	198.115	198.220
AZ	120+483.803	6.30	198.200	198.306
BA	120+486.742	6.30	198.285	198.389
BB	120+489.680	6.30	198.368	198.468
BC	120+492.619	6.30	198.450	198.542
BD	120+495.558	6.30	198.530	198.611
BE	120+498.497	6.30	198.610	198.678
BF	120+501.435	6.30	198.688	198.741
BG	120+504.374	6.30	198.765	198.801
BH	120+507.313	6.30	198.841	198.858
CL Brg. Pier 3 DS	120+509.541	6.30	198.897	198.897
CL Pier 3	120+510.000	6.30	198.909	198.909

DESIGNED	JWD
CHECKED	JJK
DRAWN	LK
CHECKED	JJK

Notes:

1. Work this sheet with Sheet No. 9 of 91 sheets.
2. All elevations and offsets are in meters (m).

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94/IL 394 SOUTH BOUND
TOP OF SLAB ELEVATIONS-3
SPANS 1-3
WB I-80/94 TO SB IL 394 - RAMP G
FAI 80/94 - FAP 332 SECTION 0203.1B
COOK COUNTY
STA. 120+796.063 STRUCTURE NO. 016-2804
DATE 3/23/05
SCALE ---

HNTB

I:\Beauchamp\CA_156\ADDN\ACTR_28_2804\cadd\sp1508146_2804.dgn
 28-MAR-2005 12:26