

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	40
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

50101440 REMOVAL OF EXISTING STRUCTURE NO. 35

LOCATION STA. 769+78	RT	EACH 1	REMARKS 3' X 1.5' RC BOX
TOTAL =			1.00

50105200 REMOVE EXISTING CULVERTS

LOCATION MAINLINE		EACH	REMARKS
STA 378+26	LT	1	(30' OF 18" CONC. W/ HDWALLS)
STA 380+56	RT	1	(39' OF 18" CONC. W/ HDWALLS)
STA. 380+81	CL	1	(49' OF 24" CONC. W/ HDWALLS)
STA 403+32	RT	1	(18' OF 15" CONC. W/HDWALLS)
STA 403+63	LT	1	(17' OF 15" CONC. W/HDWALLS)
STA 412+64	RT	1	(41' OF 12" CMP W/HDWALLS)
STA 421+70	RT	1	(19' OF 15" CONC. W/HDWALLS)
STA 448+00	LT	1	(17' OF 18" CONC. W/HDWALLS)
STA 459+78	LT	1	(40' OF 18" CONC. W/HDWALLS)
STA 497+78	RT	1	(17' OF 15" CONC. W/HDWALLS)
STA 510+03	LT	1	(18' OF 12" CONC. W/HDWALLS)
STA 513+18	LT	1	(26' OF 15" CONC. W/HDWALLS)
STA 513+54	RT	1	(19' OF 15" CONC. W/HDWALLS)
STA 520+35	RT	1	(17' OF 15" CONC. W/HDWALLS)
STA 526+70	LT	1	(25' OF 15" CONC. W/HDWALLS)
STA 539+92	RT	1	(19' OF 15" CONC. W/HDWALLS)
STA 592+83	RT	1	(63' OF 12" CONC. W/HDWALLS)
STA 645+22	RT	1	(18' OF 15" CONC. W/HDWALLS)
STA 672+00	LT	1	(27' OF 36" CONC.)
STA 695+10	LT	1	(50' OF 36" EQRS CONC.)
STA 702+97	RT	1	(43' OF 15" CONC. W/HDWALLS)
STA 717+74	RT	1	
MT MORRIS RD			
STA 128+62	CL	1	(53' OF 24" CONC. W/FL END SEC)
TOTAL =			22

51000105 PIPE HANDRAIL

LOCATION		FOOT	REMARKS
STA. 472+50 to STA. 73+54.32 (Columbine Rd.)	RT	241	
STA. 473+00 to STA. 74+15.24 (Columbine Rd.)	RT	127	
TOTAL =			368

54002020 EXPANSION BOLTS 3/4 INCH

LOCATION STA. 584+26.48 CULVERT EXTENSION	RT	EACH 16	REMARKS
TOTAL =			16

542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"

LOCATION STA. 734+13.17 to STA. 732+60.55	LT	FOOT 150	REMARKS DRAINING INTO THE CULVERT END SECTION AT STA. 732+62
TOTAL =			150

54213453 END SECTIONS 18"

LOCATION STA. 734+13.17	LT	EACH 1	REMARKS CATTLE PASS CULVERT AT STA. 732+52
TOTAL =			1

56500600 DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED

LOCATION STA. 371+11.26 STA. 373+27.76 STA. 376+05	26.7 LT 24.3 LT LT	EACH 1 1 1	REMARKS POST OFFICE -- CURB STOP, SERVICE BOX BEHIND CURB BY MORING -- CURB STOP CURB BOX
TOTAL =			3

60100915 PIPE DRAINS 6"

LOCATION VARIOUS LOCATIONS		FOOT 50	REMARKS
TOTAL =			50

60100925 PIPE DRAINS 8"

LOCATION VARIOUS LOCATIONS		FOOT 50	REMARKS
TOTAL =			50

60100935 PIPE DRAINS 10"

LOCATION VARIOUS LOCATIONS		FOOT 50	REMARKS
TOTAL =			50

60100945 PIPE DRAINS 12"

LOCATION VARIOUS LOCATIONS		FOOT 50	REMARKS
TOTAL =			50

60107600 PIPE UNDERDRAINS 4"

LOCATION		FOOT	REMARKS
STA. 370+60	LT & RT	42.3	
STA. 371+45	LT	44.6	
STA. 372+97	RT	44.2	
STA. 375+57.5	LT	42.9	
STA. 377+88		44.0	
STA. 380+00		44.0	
STA. 381+26		44.6	
STA. 381+44		44.6	
STA. 382+61		50.3	
STA. 383+69 LT, STA. 383+97 RT		65.0	INLET TO INLET
STA. 384+81.4 to STA. 385+39	RT	57.6	INLET TO INLET
STA. 385+75	LT	48.2	INLET TO INLET
STA. 386+50	RT	10.1	
STA. 386+75	LT	9.9	
STA. 388+75	LT	10.1	INLET TO INLET
STA. 388+99	RT	11.2	
STA. 391+38.7	RT	22.7	INLET TO INLET
STA. 391+40	LT	10.2	
STA. 199+68.1 LT, STA. 199+55.2 RT		35.2	INLET TO INLET, S. ASH AVE.
STA. 200+43.4		27.6	INLET TO INLET, N. ASH AVE.
STA. 219+57.6		56.2	INLET TO INLET, S. CHESTNUT AVE.
STA. 220+42.6		46.1	INLET TO INLET, N. CHESTNUT AVE.
STA. 239+38.7		30.0	INLET TO INLET, S. OAK AVE.
STA. 240+41.3	LT	38.9	N. OAK AVE.
STA. 258+92.3		27.6	INLET TO INLET, S. PLUM AVE.
STA. 259+58.2 LT, STA. 259+62.6 RT		38.5	INLET TO INLET, S. PLUM AVE.
STA. 260+61 LT, STA. 260+52 RT		32.0	INLET TO INLET, N. PLUM AVE.
STA. 279+63.4 LT, STA. 279+54.6 RT		36.6	
TOTAL =			1015.2

60255500 MANHOLES TO BE ADJUSTED

LOCATION		EACH	REMARKS
STA. 369+92	30.2 LT	1	
STA. 371+80	31 LT	1	
STA. 382+09	34.1 LT	1	
STA. 198+91	CL	1	S. ASH AVE.
STA. 241+89.5	CL	1	N. OAK AVE.
STA. 280+44.6	12.7 RT	1	N. LOCUST AVE.
STA. 280+71	CL	1	N. LOCUST AVE.
STA. 280+85	31.9 LT	1	N. LOCUST AVE.
TOTAL =			8

60406100 FRAMES & LIDS, TYPE 1, CLOSED LID

LOCATION THROUGHOUT URBAN SECTION		EACH 8	REMARKS Contingency items to be used were needed
TOTAL =			8

60500060 REMOVING INLETS

LOCATION		EACH	REMARKS
STA. 201+10	LT	1	N. ASH AVE., CIRCULAR
STA. 373+52	LT	1	
STA. 373+53	RT	1	
STA. 374+59	LT	1	
STA. 374+59	RT	1	
TOTAL =			5

PLT DATE = Tue Feb 08 14:33:10 2005
FILE NAME = C:\pwork\eta\eta\20040917\20040917.dgn
PLOT SCALE = 1/8" = 1'-0"
REFERENCE = SHEETS