

DRAINAGE SCHEDULE

CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	62
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DESCRIPTION	STATION		550A0050	550A0340	X0322033	550A0070	550A0360	X0322034	550A0090	550A0380	X0322035	550A0110	X0322525	550A0120	550A0140	X0322127	550A0160	X0322089
			12"		12" Storm Sewer	15"	15"	15" Storm Sewer	18"	18"	18" Storm Sewer	21"	21" Storm Sewer	24"	30"	30" Storm Sewer	36"	36" Storm Sewer
			TYPE 1	TYPE 2	(W.M. Req.)	TYPE 1	TYPE 2	(W.M. Req.)	TYPE 1	TYPE 2	(W.M. Req.)	TYPE 1	TYPE 2	(W.M. Req.)	TYPE 1	TYPE 1	(W.M. Req.)	TYPE 1
	FROM	TO	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)	(feet)
LT. SIDE																		
28 - MH11	371+25.00	371+67.26	38.0															
30 - MH11	200+39.91	371+67.26	13.0															
MH11 - 31A	371+67.26	372+24.68	54.0															
31A - 32	372+24.68	373+09.83	80.0															
32 - MH12	373+09.83	374+11.81			97.0													
33 - 34	220+42.75	220+42.57			48.0													
34 - MH12	220+42.57	374+11.81	8.0															
MH 12 - 35	374+11.81	374+75.52	62.0															
35 - 35A	374+75.52	375+75.00				97.0												
35A - MH15	375+75.00	376+20.39				41.0												
37 - 38	240+86.96	240+87.17			32.0													
38 - 39	240+87.17	240+41.40	40.0															
39 - MH15	240+41.40	376+20.39			16.0													
MH15 - 40	376+20.39	377+88.14								163.0								
RT. SIDE																		
1 - MH1	370+60.58	371+68.73			105.0													
2 - MH1	199+60.11	371+68.73			15.0													
MH1 - 4	371+68.73	372+39.84			67.0													
4 - MH2	372+39.84	373+57.63			113.0													
6 - 5	219+50.16	219+51.96	49.0															
5 - MH2	219+51.96	373+57.63			21.0													
MH2 - 7	373+57.63	375+20.00						158.0										
7 - MH3	375+20.00	376+16.81						93.0										
9 - 8	239+38.68	239+38.68			32.0													
8 - MH3	239+38.68	376+16.81						35.0										
MH3 - 10	376+16.81	376+92.36								71.0								
10 - 10A	376+92.36	377+88.09						90.0										
11A - 11B	258+91.76	258+92.55	30.0															
11B - 11	258+92.55	259+58.24	60.0															
11 - 10A	259+58.24	377+88.09						33.0										
10A - 40	377+88.09	377+88.14										46.0						
LT. SIDE																		
40 - MH17	377+88.14	378+60.18											68.0					
41 - 43	262+30.88	260+61.00	166.0															
43 - 42	260+61.00	260+52.00	33.0															
42 - MH17	260+52.00	378+60.18	24.0															
MH17 - 44	378+60.18	379+50.83											78.0					
44 - MH19	379+50.83	380+33.70											81.0					
45 - MH19	280+45.20	380+33.70	14.0															
MH19 - MH20	380+33.70	381+43.70														114.0		
46 - 48	280+27.09	381+44.14	67.0															
48 - MH20	381+44.14	381+43.70		27.0														
MH20 - MH21	381+43.70	382+15.77															69.0	

PLOT DATE = Tue Feb 08 14:33:39 2005
 FILE NAME = C:\projects\1230417\DRN417.dgn
 PLOT SCALE = 56.8000' / IN.
 REFERENCE = #REF#