

SUMMARY OF QUANTITIES

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1197105	BR-2 & 105-T	WHITESIDE	59	3
STA.		TO STA.		

EXISTING CONDITIONS:
CONTRACT 64421

CODE NUMBER	ITEM	UNITS	TOTAL	ROADWAY	ROADWAY	BRIDGE	CULVERT
			100% STATE QUANTITIES	RS X020-2A SEC 105 BR-2	RS 1000 SEC 105-T	RS X020-2A	RS X028-2A
60100935	PIPE DRAINS 10"	FOOT	50		50		
60100945	PIPE DRAINS 12"	FOOT	82	32	50		
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2			
60900515	CONCRETE THRUST BLOCKS	EACH	2	2			
61100605	MISCELLANEOUS CONCRETE	CU YD	1		1		
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	1		1		
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4		
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50		50		
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	8	4	4		
63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
63500105	DELINEATORS	EACH	2	2			
66300105	CALCIUM CHLORIDE APPLIED	TON	14	0	14		
66411900	TEMPORARY FENCE	FOOT	174	174			
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,230	3,600	1,630		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	17	9		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	9	6	3		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4	4		
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SO YD	209	143	66		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	514	309	205		
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL- 19.0, N50	TON	556	488	68		
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	2	1	1		
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	11	6	5		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1			1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1			1	
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.5	0.5		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5		

* SPECIALTY ITEM

•ADDITIONAL
 •CORRECTIONS
 •DON-SPEC
 •REF.
 •REV.

REVISED
 3-10-2009