

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE 1000
44004250	PAVED SHOULDER REMOVAL	SQ YD	2752	2752
48202000	BITUMINOUS SHOULDERS, SUPERPAVE	TON	870	870
48202200	BITUMINOUS SHOULDERS, SUPERPAVE 4"	SQ YD	4733	4733
48202300	BITUMINOUS SHOULDERS, SUPERPAVE 5"	SQ YD	2224	2224
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	40	40
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	46	46
54213450	END SECTIONS 15"	EACH	2	2
54213453	END SECTIONS 18"	EACH	2	2
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	12	12
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	34	34
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	4590	4590
60107600	PIPE UNDERDRAINS 4"	FOOT	7169	7169
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	765	765
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2
60244240	GRADED INLET, SPECIAL	EACH	1	1
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	5	5
60500060	REMOVING INLETS	EACH	2	2
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5	5
60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M - 6.06	FOOT	4103	4103
60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M - 6.24	FOOT	270	270
60614600	PAVED DITCH (SPECIAL)	FOOT	458	458
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	28621	28621
60622400	CONCRETE MEDIAN, TYPE SM - 6.06	SQ FT	6177	6177
60624600	CORRUGATED MEDIAN	SQ FT	1769	1769
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
* 70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	5	5
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1

PLOT DATE = Mon Mar 26 14:05:33 2005
 FILE NAME = c:\p\projects\2102280\1162280ch.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = llljg