

BITUMINOUS SCHEDULE

F.A. PROJECT NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

	70300100	70301000	X0300471	X4066414	X4066526	X4066656	35300400	31100100
Location	Short Term Pavt Marking Foot	Work Zone Pavement Marking Removal Sq Ft	Rubbilizing PCC Pavement Sq Yd	Bit Conc Surf Cse, Superpave, Mix "C", N50 Ton	Polymerized Bit Conc Surf Cse, Super, Mix "D", N70 Ton	Polymerized Bit Conc Binder Cse, Super, IL-19.0,N70 Ton	PCC Base Course 9" Sq Yd	Sub-Base Gran Matrl Type A 12" Ton
Ramp D-A / D-B Shoulders								
Sta 65 + 58 - 66 + 48				7.2				
Sta 65 + 58 - 66 + 48				9.7				
Sta 66 + 48 - 66 + 53				0.3				117.9
Sta 66 + 48 - 67 + 37					11.0	78.6		109.0
Ramp A-C / B-C Shoulders								
Sta 80 + 23 - 81 + 62					12.8	91.7		127.3
Sta 80 + 98 - 81 + 62					2.5	18.1		27.9
Sta 81 + 62 - 82 + 52				10.2				
Sta 81 + 62 - 82 + 52				6.8				
Limestone Road								
Sta 90 + 12 - 90 + 75								
Sta 90 + 23 - 90 + 75				10.4				
Sta 90 + 23 - 90 + 75				12.5				
IL 72 (At Median Noses)								
Sta 21926 + 44 - 21926 + 53					0.7		7.9	
Sta 21927 + 5 - 21927 + 89					3.4		40.6	
Sta 21939 + 63 - 21940 + 27					0.8		9.3	
Sta 21940 + 77 - 21941 + 83					3.7		44.4	
S.B. I-39 Ramp C-A / C-B								
Sta 23 + 30 - 24 + 14					5.9	42.3		48.0
S.B. I-39 Ramp A-D / B-D								
Sta 30 + 31 - 31 + 36					3.5		42.0	46.1
Sta 30 + 23 - 31 + 35					3.3	23.4		26.5
N.B. I-39 Ramp D-A / D-B								
Sta 66 + 48 - 67 + 38					6.2	44.4		50.4
N.B. I-39 Ramp A-C / B-C								
Sta 80 + 32 - 81 + 37					3.5		42.0	46.1
Sta 80 + 23 - 81 + 34					4.4	31.3		35.5
ISLANDS								
Sta 21926 + 50					0.9		11.0	
Sta 21940 + 0					0.9		11.0	
TOTALS	3,595	395	10,841	1,354	1,428	2,531	208	5,245

PLOT DATE = Mon Mar 28 14:18:38 2005
 FILE NAME = c:\prowork\216288\af6288a.dgn
 USER = jh
 USER NAME = jh