

BITUMINOUS SCHEDULE

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120RS-3	OGLE	145	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Location	Z0028415	*2001306	X4066656
	Geotechnical Reinforcement	Polymerized Bit Conc Bind Cse, Super, IL-12.5, N70	Polymerized Bit Conc Bind Cse, Super, IL-19.0, N70
	Sq Yd	Ton	Ton
Ramp D-A / D-B Shoulders			
Sta 65 + 58 - 66 + 48			
Sta 65 + 58 - 66 + 48			
Sta 66 + 48 - 66 + 53			
Sta 66 + 48 - 67 + 37		159.4	
Ramp A-C / B-C Shoulders			
Sta 80 + 23 - 81 + 62		186.2	
Sta 80 + 98 - 81 + 62		40.8	
Sta 81 + 62 - 82 + 52			
Sta 81 + 62 - 82 + 52			
Limestone Road			
Sta 90 + 12 - 90 + 75			
Sta 90 + 23 - 90 + 75			
Sta 90 + 23 - 90 + 75			
IL 72 (At Median Noses)			
Sta 21926 + 44 - 21926 + 53		7.9	
Sta 21927 + 5 - 21927 + 89		40.6	
Sta 21939 + 63 - 21940 + 27		9.3	
Sta 21940 + 77 - 21941 + 83		44.4	
S.B. I-39 Ramp C-A / C-B			
Sta 23 + 30 - 24 + 14		70.2	
S.B. I-39 Ramp A-D / B-D			
Sta 30 + 31 - 31 + 36		42.0	
Sta 30 + 23 - 31 + 35		38.8	
N.B. I-39 Ramp D-A / D-B			
Sta 66 + 48 - 67 + 38		73.7	
N.B. I-39 Ramp A-C / B-C			
Sta 80 + 32 - 81 + 37		42.0	
Sta 80 + 23 - 81 + 34		52.0	
ISLANDS			
Sta 21926 + 50		11.0	
Sta 21940 + 0		11.0	
TOTALS		7,576	999
			2,613

PLOT DATE = Mon Mar 28 14:09:28 2005
 FILE NAME = c:\pcc\pcc1a\219268\219268.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = jlljke