

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
650	104-T-1	JO DAVIESS	24	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEM	UNIT	Y007 TOTAL QUANTITY	100% STATE
* A2006514	TREE, QUERCUS BICOLOR 1-3/4" CALIPER BALLED & BURLAPPED	EACH	4	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	
20200100	EARTH EXCAVATION	CU YD	1414	
20200200	ROCK EXCAVATION	CU YD	5	
20400800	FURNISHED EXCAVATION	CU YD	636	
20800150	TRENCH BACKFILL	CU YD	789	
25000310	SEEDING, CLASS 4	ACRE	0.1	
25001830	SEEDING, CLASS 6 (MODIFIED)	ACRE	0.6	
25100115	MULCH, METHOD 2	ACRE	0.7	
25002300	TEMPORARY SEEDING	ACRE	0.7	
28000300	TEMPORARY DITCH CHECKS	EACH	8	
28000400	PERIMETER EROSION BARRIER	FOOT	1134	
28100109	STONE RIPRAP, CLASS A5	SQ YD	436	
28200100	FILTER FABRIC	SQ YD	436	
31100110	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ. YD.	264	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	
X4060414	CONCRETE BITUMINOUS SURFACE COURSE SUPERPAVE MIX C, NS0	TON	200	
44201013	CLASS B PATCHES, TYPE IV, 13"	SQ YD	266	
44213100	PAVEMENT FABRIC	SQ YD	266	
44213200	SAW CUTS	FOOT	120	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	280.0	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	4	
54010807	PRECAST CONCRETE BOX CULVERT 8' X 7'	FOOT	240	
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	36	
54213459	END SECTIONS 24"	EACH	2	
63200310	GUARDRAIL REMOVAL	FOOT	556	
63500105	DELINEATORS	EACH	2	
66411900	TEMPORARY FENCE	FOOT	1018	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	
66700305	PERMANENT SURVEY MARKER TYPE II	EACH	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	
67100100	MOBILIZATION	L SUM	1	
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1400	
28100209	STONE RIP RAP CLASS A5	TON	45	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	
Z0017200	DOWEL BARS	EACH	96	
Z0075300	TIE BARS	EACH	46	

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____

SUMMARY OF QUANTITIES

PLOT DATE = Tue Mar 29 14:52:08 2005
 FILE NAME = c:\pvc\mca\210793\18783.vp
 PLOT SCALE = 50.0000' / 1" IN.
 USER NAME = gortj