

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
650	104-T-1	JO DAVIESS	24	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

<p>20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT LOCATION OFFSET 15 1051 + 73 44' LT 15 1053 + 85 44' LT 30 TOTAL</p> <p>20800150 TRENCH BACKFILL CU.YD. LOCATION 789 1052 + 2 - 1052 + 74 789 TOTAL</p> <p>25000310 SEEDING CLASS 4 ACRE LOCATION 0.1 1050 + 0 - 1055 + 0 LT & RT 0.1 TOTAL</p> <p>25001830 SEEDING CLASS 6 (MODIFIED) ACRE LOCATION 0.6 1050 + 0 - 1055 + 0 LT & RT 0.6 TOTAL</p> <p>25002300 TEMPORARY SEEDING ACRE LOCATION 0.7 1050 + 0 - 1055 + 0 LT & RT 0.7 TOTAL</p> <p>25100115 MULCH METHOD 2 ACRE LOCATION 0.7 SEE SEEDING SCHEDULE 0.7 TOTAL</p> <p>28000300 TEMPORARY DITCH CHECK EACH LOCATION 8 1052 + 0 - 1052 + 33 LT & RT 8 TOTAL</p> <p>28000400 PERIMETER EROSION BARRIER FOOT LOCATION 567 1050 + 0 - 1055 + 0 LT 567 1050 + 0 - 1055 + 0 RT 1134 TOTAL</p> <p>28100109 STONE RIP RAP CLASS A5 SQ. YD. LOCATION 218 1050 + 0 - 1052 + 45 LT 218 1050 + 0 - 1052 + 2 RT 436 TOTAL</p> <p>28200100 FILTER FABRIC FOR USE WITH RIP RAP SQ. YD. LOCATION 436 SEE STONE RIP RAP DITCH SCHEDULE 436 TOTAL</p> <p>31100200 SUB-BASE GRANULAR MATERIAL TYPE A 12" SQ. YD. LOCATION 264 1051 + 97 - 1052 + 79 264.0 TOTAL</p> <p>44200162 CLASS B PATCHES TYPE IV 13" SQ. YD. LOCATION 266 1051 + 92 - 1052 + 84 266 TOTAL</p> <p>44213100 PAVEMENT FABRIC SQ. YD. LOCATION 266 1051 + 92 - 1052 + 84 266 TOTAL</p> <p>44213200 SAW CUTS FOOT LOCATION 24.0 1051 + 92 24.0 1052 + 84 24.0 Transverse Pressure Relief Saw Cut 24.0 1052 + 2 24.0 1052 + 74 120.0 TOTAL</p>	<p>48101200 AGGREGATE SHOULDERS TYPE B TON LOCATION 72.0 1050 + 50 - 1054 + 0 LT & RT 72.0 TOTAL</p> <p>50100300 REMOVAL OF EXISTING STRUCTURE NO.1 EACH LOCATION 1 1052 + 51.99 8.75X8 MAIN LINE 1 TOTAL</p> <p>542D0229 PIPE CULVERTS CLASS D TYPE I 24" FEET LOCATION 36 1.2 MILES NORTH OF CANYON ROAD ON FIELDER ROAD 36 TOTAL</p> <p>54213459 END SECTIONS 24" EACH LOCATION 2 1.2 MILES NORTH OF CANYON ROAD ON FIELDER ROAD 2 TOTAL</p> <p>63200310 GUARDRAIL REMOVAL FOOT LOCATION 278 1050 + 82 - 1053 + 59 LT 278 1051 + 44 - 1054 + 21 RT 556 TOTAL</p> <p>63500105 DELINEATORS EACH LOCATION 2 FIELDER ROAD (@24"PIPE REPLACEMENT) 2 TOTAL</p> <p>66411900 TEMPORARY FENCE FEET LOCATION 1018 1050 + 0 - 1055 + 0 LT & RT 1018 TOTAL</p> <p>66600105 FURNISH AND ERECT RIGHT-OF-WAY MARKERS EACH LOCATION 1 1050 + 0 42.80' LT 1 1050 + 50 65.00' LT 1 1052 + 0 100.00' LT 1 1053 + 0 100.00' LT 1 1054 + 50.00 48.00' LT 1 1050 + 0.00 40.00' RT 1 1051 50.00 100.00' RT 1 1053 + 0.00 100.00' RT 1 1054 + 50.00 40.00' RT 9 TOTAL</p> <p>66700305 PERMANENT SURVEY MARKER TYPE II EACH LOCATION 1 1057 + 10.44 39.78 LT 1 1053 + 1.00 87.00 RT 2 TOTAL</p> <p>78001110 PAINT PAVEMENT MARKING LINE 4" FOOT LOCATION 700 1050 + 50 - 1054 + 0 WHITE EDGELINES 700 1050 + 50 - 1054 + 0 DBL YELLOW 1400 TOTAL</p> <p>Z0017200 DOWEL BARS EACH LOCATION 96 1051 + 92 - 1052 + 84 96 TOTAL</p> <p>Z0075300 TIE BARS EACH LOCATION 46 1051 + 92 - 1052 + 84 CENTERLINE 46 TOTAL</p> <p>Z0005400 STONE RIP RAP CLASS A5 TON LOCATION 22 1052 + 51 LT END OF BOX 23 1052 + 16 RT END OF BOX 45 TOTAL</p>
--	---

PLOT DATE = Tue Mar 29 14:55:07 2005
 PLOT SCALE = 50.00000 / IN.
 USER NAME = goff,j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

SCHEDULE OF QUANTITIES