

SUMMARY OF QUANTITIES

CONTRACT NO. 64A10				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90% FED 10% STATE	90% FEDERAL 5% STATE 5% CITY
				ROADWAY 1000-1A	SIGNALS Y031-1F
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1036		1036
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4		4
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	141		141
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	161		161
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1050		1050
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	565		565
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 3C	FOOT	20		20
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	3		3
* 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1		1
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5		3.5
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	40.5		40.5
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10		10
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	2		2
* Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	1	
Z0017100	DOWEL BARS	EACH	112	112	
Z0023600	FILLING EXISTING CULVERTS	EACH	1	1	
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ. YD.	166	166	
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU. YD.	28	28	
Z0056900	SANITARY SEWER 8"	FOOT	60	60	

PLOT DATE = Wed Feb 09 11:41:17 2005
 FILE NAME = I:\2005\64A10\64A10.dgn
 PLOT SCALE = 50.0000 / 1" = 50.0000'
 REFERENCE = REF#

SUMMARY OF QUANTITIES