

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80		BUREAU	60	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* SECTION (06-5, 06-6, 06-7, 06 & 50-81M)				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL 10% STATE J000-2A
20200100	EARTH EXCAVATION	CU YD	5240	5240
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1010	1010
20400800	FURNISHED EXCAVATION	CU YD	1730	1730
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	276	276
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	276	276
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	276	276
25001830	SEEDING, CLASS 6 (MODIFIED)	ACRE	3.00	3.00
25100115	MULCH, METHOD 2	ACRE	3.00	3.00
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	42	42
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	566	566
28000300	TEMPORARY DITCH CHECKS	EACH	21	21
28000500	INLET AND PIPE PROTECTION	EACH	7	7
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	13882	13882
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	16476	16476
42001300	PROTECTIVE COAT	SQ YD	16476	16476
44004250	PAVED SHOULDER REMOVAL	SQ YD	3952	3952
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1950	1950
50104400	CONCRETE HEADWALL REMOVAL	EACH	8	8
50105220	PIPE CULVERT REMOVAL	FOOT	201	201
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	2647	2647
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	14	14
60107600	PIPE UNDERDRAINS 4"	FOOT	9278	9278
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	214	214
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
67100100	MOBILIZATION	L SUM	1	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4	4
70100307	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	EACH	4	4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	80	80
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	376	376
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	126	126
*78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	9133	9133
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	3558	3558
X0322288	MEDIAN CLOSURE	EACH	6	6
X0322392	BEVELED PIPE AND GUARD	EACH	12	12
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	7867	7867
Z0065752	SLOTTED DRAIN 12" WITH 6" SLOT	FOOT	755	755

\* SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. _____		DRAWN BY BRW
DATE _____		

**SUMMARY OF QUANTITIES**

DATE TIME  
JOB SPEC  
REF  
REF  
REF  
REF