

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	67TFRS-2 & I	MARSHALL	74	3
STA.		TO STA.		
FED. ROAD DIST. NO.		BLISS	FED. AID PROJECT	
D-93-065-03				

SUMMARY OF QUANTITIES					CONSTR. TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000 ROADWAY 20% STATE 80% FED	Y007 100% CITY	Y025 100% CITY	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	10.3	10.3			
20101000	TEMPORARY FENCE	FOOT	2338	2338			
20800150	TRENCH BACKFILL	CU YD	5850	5850			
* 25000300	SEEDING, CLASS 3	ACRE	0.4	0.4			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39	39			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	39	39			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	39	39			
* 25100115	MULCH, METHOD 2	ACRE	0.4	0.4			
28000400	PERIMETER EROSION BARRIER	FOOT	3304	3,304			
28100107	STONE RIPRAP, CLASS A4	SQ YD	34	34			
28200200	FILTER FABRIC	SQ YD	34	34			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3221	2983.8		237.2	
40600300	AGGREGATE (PRIME COAT)	TON	75	75			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1058	1058			
40600990	TEMPORARY RAMP	SQ YD	73	73			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	129	129			
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	11562	8597		2965	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2251	2251			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	2	2			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	44	44			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	580	580			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	765	765			
44213200	SAW CUTS	FOOT	1,575	1,575			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	459	459			
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	229	229			
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	46	46			
54207177	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	FOOT	360	331.6		28.4	
54213465	END SECTIONS 30"	EACH	1	1			
54213477	END SECTIONS 42"	EACH	1	1			
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1			
54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42"	EACH	1	1			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	47	47			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12	FOOT	113	113			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18	FOOT	1293	1293			
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	771	771			
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30	FOOT	41	41			



* INDICATES SPECIALTY ITEM
REVISED
 JUN 05 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY

SCALE: VERT. HORIZ. DRAWN BY CHECKED BY
 DATE

P.A.P. SHEET NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	6717RS-2 & I	MARSHALL	74	4
STA.	TO STA.			
FED. ROAD DIST. NO.	SLABS	FED. AID PROJECT		
D-93-065-03				

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000 ROADWAY 20% STATE 80% FED	Y007 100% CITY	100% CITY Y025
55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	126	116	10	
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	155	155		
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	786	786		
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	151	151		
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	327	301.2	25.8	
550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	1473	1356.6	116.4	
56106200	ADJUSTING WATER MAIN 4"	FOOT	275	275		
56106300	ADJUSTING WATER MAIN 6"	FOOT	75	75		
56106400	ADJUSTING WATER MAIN 8"	FOOT	80	80		
6010070	SHOULDER REMOVAL AND REPLACEMENT	SQ FT	112	112		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	7	7		
60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	12	12		
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5		
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	11	11		
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	17	17		
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	9	9		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7	7		
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	1	1		
60500050	REMOVING CATCH BASINS	EACH	1	1		
60500060	REMOVING INLETS	EACH	14	14		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2251	2251		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	254	254		
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		
* 66901000	BACKFILL PLUGS	CU YD	42	42		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5140	5140		
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25281	25281		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1880	1880		

* INDICATES SPECIALTY ITEM

⚠️ REVISED 6-6-2005

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY

SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY

APRIL 6, 2005 / e006503/SCHEDULES.DGN