

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	(126,127)RS-4	KENDALL	8	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE:		UNIT	TOTAL QUANTITY
	ITEM	I000		
20400800	FURNISHED EXCAVATION		CU YD	16
21400100	GRADING AND SHAPING DITCHES		FOOT	40
25100630	EROSION CONTROL BLANKET		SQ YD	60
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	7208
40600300	AGGREGATE (PRIME COAT)		TON	178
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS		TON	26
40600895	CONSTRUCTING TEST STRIP		EACH	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT		SQ YD	960
40600990	TEMPORARY RAMP		SQ YD	93
44000003	BITUMINOUS SURFACE REMOVAL 3/4"		SQ YD	87855
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)		SQ YD	1220
48101200	AGGREGATE SHOULDERS, TYPE B		TON	1714
50104300	CONCRETE HEADWALL REMOVAL		CU YD	0.4
50800105	REINFORCEMENT BARS		POUND	30
54002020	EXPANSION BOLTS 3/4 INCH		EACH	8
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"		FOOT	11
54213450	END SECTIONS 15"		EACH	3
54248510	CONCRETE COLLAR		CU YD	0.2
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	3
67100100	MOBILIZATION		L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	6582
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	1097
* 78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	80798
* 78001130	PAINT PAVEMENT MARKING - LINE 6"		FOOT	7440
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER		EACH	447
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	447
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50		TON	7520
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50		TON	44
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50		TON	171

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 SCALE: VERT. DATE HORIZ. DATE DRAWN BY CHECKED BY