

F. L. & MILE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1488	116.17, 118RS-2	MCLEAN	6	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GENERAL NOTES

THE THICKNESS OF BITUMINOUS MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

SHORT TERM PAVEMENT MARKING SHALL BE USED TO OUTLINE THE CENTERLINE OF ROADWAY ONLY.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

MICROSURFACING	20	LBS / SQ YD
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION

MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

- MEDIACOM
- AMEREN IP
- VERIZON
- CENTRAL ILLINOIS LIGHT CO.
- NICOR

THE CONTRACTOR SHALL DEVISE AND SUBMIT A JOINT PLAN THAT MEETS THE APPROVAL OF THE ENGINEER

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS PROJECT.

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY	CONSTR. TYPE CODE
				F000 ROADWAY 100% STATE
44800100	MICROSURFACING, 1-PASS	SQ YD	120948	120948
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4540	4540
* 78001110	PAINT PAVEMENT MARKING LINE, 4"	FOOT	98737	98737
* 78001130	PAINT PAVEMENT MARKING LINE, 6"	FOOT	11353	11353
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1513	1513
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	562	562
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	562	562

\* INDICATES SPECIALTY ITEM

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: Thomas R. Bonch  
DISTRICT STUDIES & PLANS ENGINEER

DATE: 03/14/2005

EXAMINED BY: Hubert E. [Signature]  
DISTRICT CONSTRUCTION ENGINEER

Kimberly L. [Signature]  
DISTRICT MATERIALS ENGINEER

Steven A. [Signature]  
DISTRICT OPERATIONS ENGINEER

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES  
SUMMARY OF QUANTITIES