


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	25
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SET # - BILL OF MATERIALS FOR INFORMATION ONLY					URBAN										
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(WMD)	001 90% FED 10% STATE		010 80% FED 20% STATE		001 90% FED 10% STATE		90% FED 5% STATE 5% CITY		90% FED 10% STATE		
					ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F
M281011	STONE RIPRAP, CLASS A6	SQ M	59			59									
M281025	STONE RIPRAP, CLASS B3	SQ M	309			309									
M2820100	FILTER FABRIC FOR USE WITH RIPRAP	SQ M	1,448			309									
M2850300	ARTICULATED BLOCK MAT	SQ M	312.8			312.8									
M3110010	SUB-BASE GRANULAR MATERIAL, TYPE A	M TON	4,892		4,892										
M3110100	SUB-BASE GRANULAR MATERIAL, TYPE B	M TON	252		252										
M3530240	PORTLAND CEMENT CONCRETE BASE COURSE 240MM	SQ M	8,206		8,206										
M4060200	BITUMINOUS MATERIAL (PRIME COAT)	M TON	260.4		81.6	178.8									
M4060300	AGGREGATE (PRIME COAT)	M TON	42.4		42.4										
M4060980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ M	1,337		1,337										
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	27,932		1,334	26,798									
M4205200	PROTECTIVE COAT	SQ M	100,313		1,358	92,955									
M4205050	BRIDGE APPROACH PAVEMENT SPECIAL	SQ M	827		827										
M4210290	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 290 MM	SQ M	26,691		26,691										
M4214290	PAVEMENT REINFORCEMENT 290MM	SQ M	26,691		26,691										
M4401015	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	SQ M	38,282		38,282										
M4402000	PAVEMENT REMOVAL	SQ M	69,633		141	69,492									
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	3,902		3,902										
M4402050	SIDEWALK REMOVAL	SQ M	90		90										
M4402420	MEDIAN REMOVAL	SQ M	1,329		1,329										
M4402530	PAVED SHOULDER REMOVAL	SQ M	22,672		5,376	17,296									
M4405000	PAVED DITCH REMOVAL	METER	1,036		365	671									
M4426225	CLASS B PATCHES, TYPE II, 250 MM	SQ M	767		767										
M4429400	SAW CUTS	METER	1,704		1,704										
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	2,168		2,168										
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	9,156		9,156										
M4820000	BITUMINOUS SHOULDERS	M TON	1,471		1,471										
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250 MM	SQ M	16,143		16,143										
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290 MM	SQ M	15,026		15,026										
M5010430	CONCRETE HEADWALL REMOVAL	CU M	154.8		44.2	15.6									
M5010521	REMOVE EXISTING CULVERTS	METER	47		23										
M5010522	PIPE CULVERT REMOVAL	METER	87												
M5020100	STRUCTURE EXCAVATION	CU M	6,281.0				1,283	2,782					2,216		
M5030105	NEOPRENE EXPANSION JOINT 50 MM	METER	74.6				24.4	25.5	24.7						

FOR INFORMATION ONLY



REVISIONS	
NAME	DATE
REVISED	01/31/05
MAY 27 2005	

ILLINOIS DEPARTMENT OF TRANSPORTATION
 BILL OF MATERIALS
 WAR MEMORIAL DRIVE
 FAI ROUTE 74 (I-74) (WB)
 PLAN SET #1
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04