

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SET # - BILL OF MATERIALS FOR INFORMATION ONLY				URBAN												
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	Q01 90% FED 10% STATE		Q10 80% FED 20% STATE		Q01 90% FED 10% STATE				90% FED 5% STATE 5% CITY		90% FED 10% STATE		
				ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-IF	TRAFFIC SIGNALS Y031-IF	TRAFFIC SIGNALS Y031-IF
				(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert >20	Culvert <20, R Wall				War Memorial Dr/Sterling/Olen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance
M0504002	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 1829 MM	METER	1,445.1				596.6	846.5								
M0509025	ALUMINUM RAILING TYPE H (SPECIAL)	METER	666.0			68.0	183.5	257.0		157.5						
M0637105	CONCRETE BARRIER TRANSITION, SPECIAL	CU M	5.7		5.7											
M0637112	CONCRETE BARRIER TRANSITION (MODIFIED)	METER	19.0		19											
M0720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	26.78		8.94			17.84								
M0721010	COMPOSITE TEMPORARY SIGN OVERLAY	SQ M	15.34		7.33			8.01								
M0817055	ELECTRIC CABLE IN CONDUIT, 600V 3-1/C NO. 6	METER	70												50	20
M0871055	FIBER OPTIC CABLE IN CONDUIT, NO62.5/125, MM2F SM12F	METER	2,185									2,185				
M0877019	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.46 METER	EACH	1												1	
M0877020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.76 METER	EACH	1												1	
M0878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	23.4												13.2	10.2
*4001825	BARRIER BASE	SQ M	104		104											
M2017205	DOWEL BARS 38 MM	EACH	2,366	2,366												
M2021500	EXPANSION JOINT 75 MM	METER	30		30											
M2022800	FENCE REMOVAL	METER	131		131											
M2031005	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ M	1,706.0							1,706						
M2031017	MECHANICALLY STABILIZED EARTH RETAINING WALL WITH CAST IN PLACE FACING	SQ M	1,577.0							1,577						
M2047300	PROTECTIVE SHIELD	SQ M	1,794					1,328	466							
X0323336	LED SIGNAL FACE RETROFIT, RED BALL	EACH	14											14		
X0323337	LED SIGNAL FACE RETROFIT, GREEN BALL	EACH	14											14		
X0323339	LED SIGNAL FACE RETROFIT, WALK/DONT WALK SPECIAL	EACH	2											2		
X0323481	VIDEO VEHICLE DETECTION, 4 CAMERAS	EACH	3											3		1
X0323418	LED SIGNAL FACE RETROFIT, YELLOW BALL	EACH	14											14		
X0324134	BATTERY BACKUP SYSTEM WITH CABINET	EACH	3											3		1
X0323419	LED SIGNAL FACE RETROFIT, YELLOW ARROW	EACH	14											14		
X0323420	LED SIGNAL FACE RETROFIT, GREEN ARROW	EACH	14											14		
X0323483	LED SIGNAL FACE RETROFIT, RED ARROW	EACH	8											8		
X0323677	STREET SWEEPING	HOUR	482		482											
X0323678	DUST CONTROL PADS	EACH	2		2											
X0323778	DRAINAGE SCUPPERS, TYPE 1	EACH	6			2	4									
X0323779	DRAINAGE SCUPPERS, TYPE 2	EACH	12				4	8								
X0323989	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY	EACH	20		9			11								
XT015000	CHANGEABLE MESSAGE SIGN	CAL MD	24		24											
XB800020	SIGNAL HEAD, LED, 1 - FACE, 3 - SECTION, MAST ARM MOUNTED	EACH	16												10	6

FOR INFORMATION ONLY



REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION
BILL OF MATERIALS
 WAR MEMORIAL DRIVE
 FAI ROUTE 74 (I-74) (WB)
 PLAN SET #1
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04