F.A. - RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	103
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY SIGN

LOCATIONS	STA	TO STA	OFFSET	RT/LT	TYPE	NO OF SIGN	SIZE SQ M	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY RTSPA EA	COMPOSITE TEMPORARY SIGN OVERLAY CTSO SQ M	SIGN PANEL OVERLAY, SPECIAL SPO(S) SQ M	TEMPORARYSIGN PANEL OVERLAY TSPO SQ M	TEMPORARYSIGN PANEL ASSEMBLY TSPA SQ M	REMOVE SIGN PANEL ASSEMBLY TYPE B RSPA EACH	REMOVE SIGN PANEL ASSEMBLY TYPE A RSPA EACH
STAGE 3-1, 3-2, 3-3														
STAGE 3-1														
WAR MEMORIAL DRIVE														
Sterling Avenue	100+950			RT	RSPA								1.00	
North Mall	9+910			LT	RTSPA			1						
	9+970			LT	TSPA							0.68		
War Memorial	38+870			RT	RTSPA			1						
	38+990			RT	RTSPA			1						
	39+075			RT	TSPA							1.00		
				RT	RSPA								1.00	
	39+085			RT	RSPA								1.00	
	39+310			LT	TSPA							1.00		
				LT	RSPA								1.00	
	39+380			RT	RTSPA			1						
	39+425			RT	RSPA								2.00	
	39+515			RT	CTSO				0.85					
	39+610			RT	TSPO							0.72		
	39+775			RT	CTSO				0.85					
	39+920			LT	TSPA							0.94		
	40+150			LT	RSPA								1.00	
				LT	CTSO				0.85					
	40+350			LT	SPO					0.18				
				LT	SPO					8.46				REMOVAL ONLY
				LT	CTSO				0.96					
	40+470			LT	SPO					0.90				REMOVAL ONLY
	40+620			LT	CTSO				2.50					
				LT	SPO						5.30			REMOVAL ONLY
				LT	CTSO				0.96					
				LT	SPO						0.18			
				LT	SPO						7.84			REMOVAL ONLY
SUBTOTAL	J000-2A							4	6.97	9.54	13.32	4.34	7.00	
STAGE 3-2.1, 3-2.2, 3-2.3 & 3-3														
FAI ROUTE 74 WEST BOUND														
WB	142+240			LT	TSPA							1.40		
SUBTOTAL	J000-2A							0	0.00	0.00	0.00	1.40	0.00	
STAGE 3-2														
WAR MEMORIAL DRIVE														
War Memorial	39+555			RT	RTSPA			1						
	39+620			RT	RTSPA			1						
SUBTOTAL	J000-2A							2	0.00	0.00	0.00	0.00		
STAGE 3-3														
WAR MEMORIAL DRIVE														
Sterling Avenue	100+890			LT	SPO					0.68				
War Memorial	38+950			RT	TSPA							2.03		
	39+075			LT	RTSPA			1						
	39+140			LT	TSPA							2.03		
				RT	RTSPA			1						
North Mall	9+910			LT	RSPA								3.00	
SUBTOTAL	J000-2A							2	0.00	0.68	0.00	4.06	3.00	
ROUNDED TOTAL														

REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005

PARSONS TRANSPORTATION GROUP
Engineers and Planners

ILLINOIS DEPARTMENT OF TRANSPORTATION

TEMPORARY SIGN SCHEDULE

FAI ROUTE 74 (I-74) (WB)

DRAWN BY CADD

DATE 11/12/04

CHECKED BY RSC