F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	255
STA. 39+850.000		TO STA. 40+175.000		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LEGEND

BITUMINOUS SHOULDERS

PAVEMENT WIDENING

NOTE:

1. SEE INTERSECTION DETAIL SHEETS.

SIGN

PR PCC SHOULDER, 250mm

PR PCC PAVEMENT, 250mm (JOINTED)

CONSTRUCTION LIMITS (TYP)

BRANDYWINE DR.

PR CONCRETE BARRIER DOUBLE FACE (SPECIAL)

STA 10+695.993 (RAMP B-3) PR TRAFFIC BARRIER TERMINAL TY 1 SPECIAL

PR STEEL PLATE GUARDRAIL TY A

PR TRAFFIC BARRIER TERMINAL TY 6

END CONCRETE BARRIER DOUBLE FACE (SPECIAL) 10+900.000 (RAMP B-3)

MATCH LINE STA. 10+975.000 (RAMP B-3)

℄ RAMP B-3

℄ RAMP B-5

PAVED DITCH (EXISTING)

OVERHEAD SIGN BASE

UG UTIL

38mm POLYMERIZED BIT CONC SURFACE COURSE SUPERPAVE, MIX E, N70
57mm POLYMERIZED BIT CONC BINDER COURSE SUPERPAVE, IL-19.0, N70

PR PORTLAND CEMENT CONCRETE PAVEMENT, 250mm (JOINTED)

STA 10+390.636 (RAMP B-5) PR TRAFFIC BARRIER TERMINAL TY 1 SPECIAL

40+086.821 11.800 LT

2.4m BITUMINOUS CONCRETE

COMB CC & G TY SB-15.30 (TYP.)

STA 10+035.512 (RAMP B-5) BEGIN PR PCC SHOULDER, 250mm

40+026.573 15.080 LT

39+942.574 15.031 LT

℄ WAR MEMORIAL DR.

LANDSCAPED MEDIAN (TYP.)

BEGIN RAMP B-5 STA. 10+023.170

MATCH LINE STA. 39+850.000 (WAR MEMORIAL DR)

39+852.365 11.800 LT

STA. 39+965.140 4.25m LT.

STA. 39+965.444 3.96m RT.

STA. 40+087.399 4.20m LT.

STA 10+000.000 (B-6) BEGIN PR PCC SHOULDER, 250mm

END MSE WALL #11 10+574.614 (RAMP B-3)

BEGIN PR CONCRETE GUTTER TYPE A (MODIFIED), STA 10+012.234

STR. 072-0190 SEE BRIDGE PLANS

PR PCC PAVEMENT 250mm (JOINTED)

MATCH LINE STA. 10+550.000 (RAMP B-5) STA 190+555.56 (RAMP B-3)

CONSTRUCTION LIMITS (TYP)

38mm POLYMERIZED BIT CONC SURFACE COURSE SUPERPAVE, MIX E, N70
57mm POLYMERIZED BIT CONC BINDER COURSE SUPERPAVE, IL-19.0, N70 (TYP)

PROPOSED 2.750m DIAMETER PIPES (JACKED-IN-PLACE)

COMB CC & G TYB-15.60 (TYP.)

STA. 39+865.413 4.00m RT.

STA. 39+865.413 4.00m RT.

PR TRAFFIC BARRIER TERMINAL TY1

12.00m RADIUS

PERMANENT EASEMENT

TEMP. EASEMENT

STA. 39+910.00, 45 .00m RT END PR STEEL PLATE GUARDRAIL TY A

EXISTING R.O.W. & A

38mm POLYMERIZED BIT CONC SURFACE COURSE SUPERPAVE, MIX E, N70
57mm POLYMERIZED BIT CONC BINDER COURSE SUPERPAVE, IL-19.0, N70

PR PORTLAND CEMENT CONCRETE PAVEMENT, 250mm (JOINTED)

88mm BIT SURFACE OVERLAY

MATCH LINE STA. 40+175.000 (WAR MEMORIAL DR)

PR PCC SHOULDER, 250mm

MATCH LINE STA. 10+075.000 (RAMP B-6)

℄ RAMP B-6

0 5 10 15 20 25

1m : 500m

PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005
REVISED SHEET	

ILLINOIS DEPARTMENT OF TRANSPORTATION

PROPOSED ROADWAY PLAN

WAR MEMORIAL DRIVE

STA. 39+850.000 - STA. 40+175.000

DRAWN BY CADD

DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\shtwb\rp0016-IgWM.DGN