F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	883
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET #2 BILL OF MATERIALS
FOR INFORMATION ONLY

				URBAN													
				Q01 90% FED 10% STATE			Q10 80% FED 20% STATE	Q01 90% FED 10% STATE							90% FED 5% STATE 5% CITY		90% FED 10% CITY
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	1,026.3		1,026.3												
M2800400	PERIMETER EROSION BARRIER	METER	945		945												
M2810107	STONE RIPRAP, CLASS A4	SQ M	86		86												
M2820100	FILTER FABRIC FOR USE WITH RIPRAP	SQ M	2,175		2,175												
M2850300	ARTICULATED BLOCK MAT	SQ M	2,089		2,089												
M3110010	SUB-BASE GRANULAR MATERIAL, TYPE A	M TON	2		2												
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	68.1		68.1												
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	3,052		3,052												
M4205200	PROTECTIVE COAT	SQ M	34,354		34,354												
M4210290	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 290MM	SQ M	19,574		19,574												
M4214290	PAVEMENT REINFORCEMENT 290MM	SQ M	19,574		19,574												
M4402000	PAVEMENT REMOVAL	SQ M	28,144		28,144												
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	92		92												
M4402530	PAVED SHOULDER REMOVAL	SQ M	1,147		1,147												
M4405000	PAVED DITCH REMOVAL	METER	257		257												
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	508		508												
M4830200	PORTLAND CEMENT CONCRETE SHOULDERS - 200MM	SQ M	5		5												
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250MM	SQ M	1,454		1,454												
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290MM	SQ M	10,043		10,043												
M5010240	CONCRETE REMOVAL	CU M	698.9						698.6	0.3							
M5020100	STRUCTURE EXCAVATION	CU M	8,476							8,476							
M5030350	CONCRETE STRUCTURES	CU M	222.9							222.9							
M5030360	CONCRETE SUPERSTRUCTURE	CU M	67.8							67.8							
M5080105	REINFORCEMENT BARS	KG	152,060						151,950	110							
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	26,210		30				790	25,390							
M5110100	SLOPE WALL 100MM	SQ M	450		450												
M5403000	CONCRETE BOX CULVERTS	CU M	1,541.7						1,541.7								
M5403220	EXPANSION BOLTS M20	EACH	208						208								
M5429910	CONCRETE COLLAR	CU M	1.0		1.0												
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	1		1												
M542E152	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1200MM	EACH	1		1												
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	65.0		65.0												
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	18.0		18.0												
M5500485	STORM SEWERS, CLASS A, TYPE 2 900MM	METER	4.5		4.5												

* SPECIALTY ITEMS
\+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
△ NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183
(4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005)
(5) WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
(6) WAR MEMORIAL DRIVE / STERLING / GLEN
(7) WAR MEMORIAL DRIVE / SCENIC DRIVE
(8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS		
	NAME	DATE
△	ADDENDUM #1	MAY 27 2005

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

TOTAL BILL OF MATERIALS
PLAN SET #2

FAI ROUTE 74 (I-74)

DRAWN BY RDY
DATE 11/23/04 CHECKED BY LSA