

FOR INFORMATION ONLY


SET #3 TOTAL BILL OF MATERIALS
LIGHTING, SIGNING & ITS

URBAN																	
IM																	
90% FED 10% STATE										90% FED 5% STATE 5% CITY				90% FED 10% STATE			
ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	BIT	CONC	A3	B3/B5	B1/B4	CULVERT >20	CULVERT<20, R WALL				WAR MEMORIAL DR/ STERLING/GLEN	WAR MEMORIAL DR/ SCENIC DR	SCENIC DR/ MALL ENTRANCE	
M7200300	SIGN PANEL - TYPE 3	SQ M	262	92	16												
M7270100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	KG	3450	3050	400												
M7290100	METAL POST - TYPE A	METER	8.5	8.5													
M7290200	METAL POST - TYPE B	METER	17.0	13.0	4.0												
M7300100	WOOD SIGN SUPPORT	METER	265.5	239.5	26.0												
M7330050	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-S (1.22M X 1.37M)	METER	63.5								63.5						
M7330255	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (0.90M x 2.14M)	METER	22.6								22.6						
M7340100	CONCRETE FOUNDATIONS	CU M	11.9	9.8	2.1												
M7340200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	64.4								64.4						
M8080150	TEMPORARY WOOD POLE, 15.24M, CLASS 4	EACH	10									10					
M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	1134.0									930.0	204.0				
M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	4069.0									4069.0					
M8101450	CONDUIT PUSHED, 50MM DIA., PVC	METER	173.0										173.0				
M8101470	CONDUIT PUSHED, 75MM DIA., PVC	METER	17.0										17.0				
M8110130	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA. GALVANIZED STEEL	METER	436.0										436.0				
M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50MM DIA. PVC	METER	179.0										179.0				
M8120250	CONDUIT EMBEDDED IN STRUCTURE, 75MM DIA. PVC	METER	494.0										494.0				
M8130120	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 150MM X 150MM X 100MM	EACH	46										46				
M8130415	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 300MM X 300MM X 200MM	EACH	13										13				
M8131500	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 675MM X 400MM X 300MM	EACH	3										3				
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	4969.5										4847.0	122.5			
M8170030	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.8	METER	2927.0										2927.0				
M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.6	METER	5124.0										5124.0				

I:\projects\data3573\contract 10 packag\ing\PS&E\Set for DST combined\Plans\sg1002-7adgn 3/4/38 PM 5/5/2005

* SPECIALTY ITEMS
+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
D NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183



REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27, 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION
SET 3
TOTAL BILL OF MATERIALS
DRAWN BY DJK
CHECKED BY DPA
DATE: 11/15/04