

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	1184
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FOR INFORMATION ONLY

SET #3 TOTAL BILL OF MATERIALS  
LIGHTING, SIGNING & ITS

				URBAN										90% FED 10% STATE			90% FED 5% STATE 5% CITY			90% FED 10% STATE		
				ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	BIT	CONC	A3	B3/B5	B1/B4	CULVERT >20	CULVERT <20, R WALL			WAR MEMORIAL DR/STERLING/GLEN	WAR MEMORIAL DR/SCENIC DR	SCENIC DR/MALL ENTRANCE							
M8170050	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.4	METER	4834.0																			
M8170060	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	METER	14439.0																			
M8170070	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	METER	75.0																			
M8170090	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	METER	48.0																			
M8180140	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	METER	512.0																			
M8300415	LIGHT POLE, ALUMINUM, 13.5M M.H., 2.4M DAVIT ARM	EACH	3																			
M8301815	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 13.5M M.H., 2.4M DAVIT ARM	EACH	32																			
M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	87.5																			
M8370100	LIGHT TOWER FOUNDATION	METER	205.3																			
M8370110	LIGHT TOWER FOUNDATION (SPECIAL)	METER	12.5																			
M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	METER	113.0																			
M8780300	CONCRETE FOUNDATION, TYPE E 600MM DIAMETER	METER	2.5																			
MX033456	NONINTRUSIVE DETECTOR POLE 9.1 METER	EACH	1																			
MX733010	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-S (0.90M x 1.68M)	METER	7.9								7.9											
MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	113.0																			
X0323920	POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1																			
X0323970	UNDERPASS LUMINAIRE, (INSTALL ONLY)	EACH	29																			
X0323971	HIGH MAST LUMINAIRE, (INSTALL ONLY)	EACH	183																			
X0323997	SIGN SUPPORT, PARAPET MOUNTED, TYPE 1	EACH	2	2																		
X8350100	LIGHT TOWER, INSTALL ONLY	EACH	34																			
XX004187	INSTALL CONTROLLER	EACH	2																			

I:\projects\data3573\contract 10 packagng\PS&E\Set For DST combined\Plans\sp003-7\adgn 3:18:06 PM 5/15/2005

- \* SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE Y080
- +++ FUND CODE SFTY-3C
- D NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183

REVISIONS	
NAME	DATE
ADDENDUM #1	MAY 27 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SET 3**  
**TOTAL BILL OF MATERIALS**  
 DRAWN BY DJK  
 CHECKED BY DPA  
 DATE: 11/15/04

