


F.A. - RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	52
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	STA	TO	STA	LENGTH M	WIDTH M	AREA (CADD CALCS) SQ M	TEMPORARY EROSION CONTROL SEEDING KG	SEEDING CLASS 7 HA	MULCH METHOD 2 HA	TEMPORARY EROSION CONTROL SCHEDULE		
										EROSION CONTROL BLANKET SQ M	EROSION CONTROL BARRIER M	FENCE (EROSION CONTROL) M
STAGE 3							4 app at 110kg/Ha					
MAINLINE												
I-74 MAINLINE, WB	141+900.000	TO	141+950.000	50.00		295.00		0.03	0.03			
I-74 MAINLINE, WB	141+950.000	TO	142 + 300.000	350.00		2,087.50		0.21	0.21	12.00		
I-74 MAINLINE, WB	142 + 300.000	TO	142 + 650.000	350.00		5,690.00		0.57	0.57			
I-74 MAINLINE, WB	142 + 650.000	TO	143 + 000.000	350.00		1,643.75		0.16	0.16			
I-74 MAINLINE, WB	143 + 000.000	TO	143 + 300.000	300.00		956.25		0.10	0.10			65.00
I-74 MAINLINE, WB	143 + 300.000	TO	143 + 650.000	350.00		570.00		0.06	0.06			
I-74 MAINLINE, WB	143 + 650.000	TO	143 + 950.000	300.00		0.00		0.00	0.00			355.00
I-74 MAINLINE, WB	143 + 950.000	TO	144 + 250.000	350.00		4,978.75		0.50	0.50			770.00
I-74 MAINLINE, WB	144 + 250.000	TO	144 + 325.000	75.00		303.75		0.03	0.03			
I-74 MAINLINE, WB	144 + 325.000	TO	144 + 600.000	275.00		1,045.00		0.10	0.10			300.00
I-74 MAINLINE, WB	144 + 600.000	TO	144 + 718.000	118.00		677.70		0.07	0.07			125.00
STAGE 3 SUBTOTAL:							0	1.8	1.8	12.0	0	1,615
RAMPS												
Ramp A-3	10+225.000	TO	10+375.000	150.00		2,815.00		0.28	0.28			
Bridge	10+375.000	TO	10+450.000	75.00								
	10+450.000	TO	10+700.000	250.00		5,317.50		0.53	0.53			
Ramp A-4	10+345.280	TO	10+371.000	25.72								
	10+371.000	TO	10+490.000	119.00								
	10+490.010	TO	10+635.290	145.30								
Ramp B-1	10+200.000	TO	10+625.000	425.00		8,977.50		0.90	0.90			
	10+625.000	TO	10+875.000	250.00								
	10+875.000	TO	11+125.000	250.00		2,751.25		0.28	0.28			
Ramp B-2	10+450.000	TO	10+600.000	150.00		2,908.75		0.29	0.29			
	10+600.000	TO	10+754.300	154.30		3,744.68		0.37	0.37			
Ramp B-3	10+175.000	TO	10+375.000	200.00		1,040.00		0.10	0.10			
	10+375.000	TO	10+575.000	200.00		1,841.25		0.18	0.18			
	10+586.000	TO	10+700.000	114.00								
	10+700.000	TO	11+000.000	300.00		4,976.25		0.50	0.50			
	11+000.000	TO	11+156.000	156.00		7,689.10		0.77	0.77			
I/C Grading A-3/B-5/B-3						1,250.00		0.13	0.13			
I/C Grading WMD/B-5/B-3						2,100.00		0.21	0.21			
Ramp B-4	10+013.000	TO	10+250.000	237.00		1,440.95		0.14	0.14			
	10+250.000	TO	10+475.000	225.00								
	10+475.000	TO	11+044.000	569.00		6,659.55		0.67	0.67			445.00
I/C Grading WMD/B-4/B-6						1,800.00		0.18	0.18			
Ramp B-5	10+062.950	TO	10+425.000	362.05		7,088.22		0.71	0.71			
	10+425.000	TO	10+550.000	125.00								
	10+550.000	TO	11+050.000	500.00		3,192.50		0.32	0.32			
Ramp B-6	10+020.730	TO	10+175.000	154.27		186.45		0.02	0.02			
	10+175.000	TO	10+203.450	28.45		661.40		0.07	0.07			
RAMPS SUBTOTAL:							0	6.6	6.6		0	445

LOCATION	OFFSET	INLET AND PIPE PROTECTION
STATION	TO	STATION
141+900.000	TO	141+950.000
141+950.000	TO	142+300.000
142+300.000	TO	142+650.000
10+324.340	TO	10+499.020
10+021.520	TO	10+146.230
10+829.200	TO	10+977.000
10+028.800	TO	10+190.010
10+700.000	TO	10+850.000
142+650.000	TO	143+000.000
143+000.000	TO	143+300.000
143+000.000	TO	143+650.000
143+650.000	TO	143+950.000
143+950.000	TO	144+250.000
144+250.000	TO	144+600.000
144+600.000	TO	144+718.000
WAR MEMORIAL DR		
38+765.000	TO	39+150.000
39+150.000	TO	39+500.000
39+500.000	TO	39+850.000
39+850.000	TO	40+175.000
40+175.000	TO	40+500.000
Total for 1000-2A		96
Total for J000-2A		141
STAGE 3 TOTAL:		237



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TEMPORARY EROSION CONTROL SCHEDULE
FAI ROUTE 74 (I-74) (WB)

DATE 11/12/04

DRAWN BY CADD
CHECKED BY RSC