


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7R-3)	PEORIA	1360	65
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

MAINLINE PAVEMENT SUMMARY				LENGTH	WIDTH	AREA (CADD CALCS)	CONTINUOUSLY REINFORCED PCC PAVEMENT 250 MM	PAVEMENT REINFORCEMENT 250 MM	PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED) 250 MM	PORTLAND CEMENT CONCRETE SHOULDERS 250 MM	PORTLAND CEMENT CONCRETE SHOULDERS 250 MM	WHITENASH	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	BRIDGE APPROACH PAVEMENT, SPECIAL	PORTLAND CEMENT CONCRETE BASE COURSE 240 MM	TOTAL AREA			
LOCATION	STA	TO	STA	M	M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M			
STAGE 3																			
Cadd																			
LT RT LT RT LT RT																			
Ramp B-5	10+062.000	TO	10+150.000	88.00	4.9				431.20										
	10+150.000	TO	10+225.000	75.00	4.9				367.50										
	10+225.000	TO	10+275.000	50.00	4.9				245.00										
	10+275.000	TO	10+403.000	128.00	4.9				627.20										
Approach Bridge	10+410.562	TO	10+419.562	9.00	3.185														
Approach	10+419.562	TO	10+505.385	85.82	3.185														
	10+505.385	TO	10+514.385	9.00	3.185														
	10+514.385	TO	10+680.000	165.62	4.9				764.40										
	10+680.000	TO	10+725.000	45.00	4.9				220.50										
	10+725.000	TO	10+905.000	180.00	4.9				882.00										
	10+905.000	TO	11+063.953	158.95	4.9				778.92										
Ramp B-5	10+418.052	TO	10+475.000	56.95	4.9				132.05										
Side Left	10+475.000	TO	10+060.000	11.00	Var				38.50										
	10+060.000	TO	10+167.000	107.00	4.9				450.80										
	10+167.000	TO	10+203.337	36.34	4.9				178.05										
RAMPS SUBTOTAL:							0	0	26,798	0	0	7,172	8,971	45,294	36,894.6	827	0		
WAR MEM DRIVE	38+985.070	TO	39+025.000	39.93	Var	118.86													
	39+025.000	TO	39+450.000	425.00	Var	850.00													
	39+450.000	TO	39+474.323	24.32	Var	448.55													
	39+474.323	TO	40+009.618	435.30	Var	304.71													
Ramp B-5 Widen	39+482.365	TO	39+531.624	49.26	Var														
	39+531.624	TO	39+582.519	50.90	Var														
	39+582.519	TO	40+026.513	43.99	3.6														
	40+026.513	TO	40+086.822	60.31	Var														
Ramp B-6 Widen	39+551.513	TO	39+624.676	73.16	Var														
	39+624.676	TO	39+674.316	49.64	Var														
	39+674.316	TO	39+689.274	14.96	Var														
	39+689.274	TO	39+694.262	204.99	Var														
	39+694.262	TO	40+009.618	215.36	Var														
	40+009.618	TO	40+376.670	267.05	Var	974.74													
	40+376.670	TO	40+456.668	47.00	Var														
	40+456.668	TO	40+517.998	153.33	Var														
	40+517.998	TO	40+546.811	28.81	Var														
Guardrail Erosion Control Aggregate	39+900.000	TO	40+175.000	275.00									56.30						
	40+175.000	TO	40+480.820	305.82															
WAR MEM DR SUBTOTAL:							0.00	0.00	0.00	0.00	0.00	0.00	0.00	56.3	0.00	3,269.57	4,202.77		
SCENIC DRIVE	10+050.000	TO	10+288.277	238.28	19.34														
LT	10+109.196	TO	10+238.738	129.54	Var	617.58													
	10+238.738	TO	10+288.277	49.54	Var	253.64													
MALL ACCESS	09+936.557	TO	09+965.557	29.00	8.1														
BRANDYWINE DR	39+385.798	TO	39+458.410	72.61	Var	86.41													
Entrance	101+036.000	TO	101+181.340	145.34	Var	332.55													
GLEN AVENUE	39+346.675	TO	39+391.760	45.08	Var	186.13													
STAGE 3 SUBTOTAL:							26,691	26,691	27,932	8,905	6,121	7,172	8,971	88,069	76,307.4	827	8,206		
WB I-74 SUBTOTAL:							26,691	26,691	27,932	8,905	6,121	7,172	8,971	88,069	76,307.4	827	8,206	41,717	
RAMPS SUBTOTAL:							-	-	26,798	-	-	7,172	8,971	45,294	36,894.6	827	-	42,941	
WAR MEM DR SUBTOTAL:							-	-	-	-	-	-	-	-	56.3	-	-	7,472	
SCENIC DR SUBTOTAL:							-	-	871	-	-	-	-	-	-	-	-	199	
MALL ACCESS SUBTOTAL:							-	-	263	-	-	-	-	-	-	-	-		
BRANDYWINE DR SUBTOTAL:							-	-	-	-	-	-	-	-	-	-	86		
FRONTAGE RD SUBTOTAL:							-	-	-	-	-	-	-	-	-	-	186		
GLEN AVE SUBTOTAL:							-	-	-	-	-	-	-	-	-	-	333		
SUBTOTAL							26,691	26,691	27,932	8,905	6,121	7,172	8,971	88,069	76,307.4	827	8,206	84,558	
Total							26,691	26,691	27,932	8,905	6,121	7,172	8,971	88,069	76,307.4	827	8,206	84,558	
Total for I000-2A							-	-	1,134	-	-	-	-	-	-	-	-	-	-
Total for J000-2A							26,691	26,691	26,798	8,905	6,121	7,172	8,971	88,069	76,251.1	827	-	-	



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 CONCRETE PAVEMENT SCHEDULE
 FAI ROUTE 74 (I-74) (WB)
 DATE 11/12/04
 DRAWN BY CADD
 CHECKED BY RSC