

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	190-11R-29003,4,11-1R-1	TAZEWELL	1366	94
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

**TRAFFIC PROTECTION SCHEDULE**

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 2 (EACH)	TERMINAL MARKERS - DIRECT APPLIED (EACH)	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2 (EACH)	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3 (EACH)
MAINLINE				
153+202.437 LT		1		1
RAMP J-3				
10+235.516 LT		1		1
RAMP J-4				
10+119.600 RT		1		1
RAMP K-2				
10+064.344 RT	1			
10+101.030 LT		1	1	
10+370.000 RT		1	1	
<b>TOTAL</b>	<b>* 1</b>	<b>5</b>	<b>2</b>	<b>3</b>

**CURB AND GUTTER SCHEDULE**

LOCATION	CLASS SI CONC OUTLET (CU M)	CONCRETE GUTTER TYPE A (METER)	CONCRETE GUTTER TYPE A (MODIFIED) (METER)	CONCRETE CURB & GUTTER B-15.45 (METER)
RAMP J-3				
10+145.073 TO 10+235.516 LT			90.4	
10+250.000 TO 10+275.000 RT			25.0	
STA. 10+275.000 RT	2.7			
RAMP J-4				
10+065.000 TO 10+322.209 LT			257.2	
RAMP K-2				
10+052.874 TO 10+085.874				33.0
10+085.874 TO 10+178.600 RT			92.7	
10+344.000 TO 10+378.450 RT			34.4	
10+378.450 TO 10+507.550 RT		139.6		
<b>TOTAL</b>	<b>* 2.7</b>	<b>* 139.6</b>	<b>499.7</b>	<b>33.0</b>

**DUST CONTROL**

LOCATION	STREET SWEEPING (HOUR)	APPLY DUST SUPPRESSION AGENTS (UNIT)	SOIL STABILIZER (KG)	DUST CONTROL PADS (EACH)
MAINLINE				
152+445.837 TO 152+700.000	52	70	1350	4
152+700.000 TO 153+000.000	52	70	1350	4
153+000.000 TO 153+300.000	52	70	1350	4
153+300.000 TO 153+600.000	52	70	1350	4
153+600.000 TO 153+892.180	52	70	450	4
RAMP J-3	49	69	1350	4
RAMP J-4	49	68	4500	4
RAMP K-2				
10+052.874 TO 10+352.500	52	70	1350	4
10+352.500 TO 10+654	52	70	450	4
<b>TOTAL</b>	<b>* 462</b>	<b>* 627</b>	<b>* 13500</b>	<b>* 36</b>

**CONCRETE SHALE CAP SCHEDULE**

LOCATION	CLASS SI CONCRETE SPECIAL (CU M)
RAMP J-3	
STA. 10+175 TO 10+350	154.2
<b>TOTAL</b>	<b>154.2</b>

ESTIMATED LIMITS WHERE SHALE MAY BE ENCOUNTERED PER GEOTECHNICAL SOILS REPORT

**CHAIN LINK FENCE SCHEDULE**

STATION	TO	STATION	CHAIN LINK FENCE 1.2 METER (METER)
MAINLINE			
153+750.100, 14.3M LT	TO	153+827.930, 14.3M LT	121.0
RAMP J-4			
10+332.000, 25.3M RT	TO	10+332.580, 3.9M RT	21.4
10+387.110, 25.2M RT	TO	10+387.820, 3.9M RT	21.3
<b>TOTAL</b>			<b>* 163.7</b>

**NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)**

**REVISIED NOTE**

REVISIONS	
NAME	DATE
△	MAY 27 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 I-74 WB  
 RAMPS J-3 & J-4

**URS**  
 URS CORPORATION  
 ST. LOUIS, MO

DRAWN BY CGF  
 CHECKED BY RLS  
 DATE 12-20-04

DATE: \$DATE-TIME HERES \$TIME HERES \$IGN FILE NAME GOES HERE SIZE IS LARGE ENOUGH FOR LONG FILE NAMES\$

10/25/2005 11:35:35 AM