

I:\projects\roadway\temp\101-5a.dgn 7/29/2005 8:57:03 AM

* L1 IS THE POST CLOSEST TO THE ROADWAY EDGE OF PAVEMENT
 ** FOR INFORMATION ONLY ITEM INCLUDED IN TEMPORARY SIGN ITEMS

BILL OF MATERIALS - TEMPORARY SIGNING

(SHEET 3 OF 5)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	342
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(90-11)R-2:90(13, 14, 14-1)R-1

LOCATION	STATION	SIGN DIMENSIONS		COMPOSITE TEMPORARY SIGN OVERLAY (SQ m)	SIGN PANEL OVERLAY (SPECIAL) (SQ m)	WOOD SIGN SUPPORT **		CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT ** (EACH)	MOUNTING		REMOVE SIGN PANEL ASSEMBLY TYPE A (EACH)	REINSTALL TEMP SIGN PANEL ASSEMBLY (EACH)	RELOCATE SIGN PANEL ASSEMBLY TYPE B (EACH)	TEMP SIGN PANEL ASSEMBLY (SQ m)	LEGEND	SIGN DETAIL	COMMENTS	
		HEIGHT (mm)	WIDTH (mm)			L1 (m)	L2 (m)		HT. ABOVE E/P (m)	OFFSET FROM E/P (m)								
MAIN ST. STAGE 3A-1 (PRE-STAGE 3)																		
LT	2+520	305	610											0.2	EAST	10	TSPA	
LT	2+520	610	610			4.1		1	1.8	4.0				0.4	I-74		TSPA	
LT	2+520	381	533											0.2	←		TSPA	
RT	2+995	600	750											0.5	WORK ZONE		TSPA	
RT	2+995	750	600			4.9		1	1.8	4.0				0.5	SPEED LIMIT 40	11	TSPA	
RT	2+995	450	1000											0.5	\$XXX FINE MINIMUM		TSPA	
RT	3+415	600	750											0.5	WORK ZONE		TSPA	
RT	3+415	750	600			4.9		1	1.8	4.0				0.5	SPEED LIMIT 40	11	TSPA	
RT	3+415	450	1000											0.5	\$XXX FINE MINIMUM		TSPA	
LT	3+530	600	750											0.5	WORK ZONE		TSPA	
LT	3+530	450	1000			4.9		1	1.8	4.0				0.5	SPEED LIMIT 40	11	TSPA	
RT	3+840	600	750											0.5	\$XXX FINE MINIMUM		TSPA	
RT	3+840	750	600			4.9		1	1.8	4.0				0.5	WORK ZONE		TSPA	
RT	3+840	450	1000											0.5	SPEED LIMIT 40	11	TSPA	
RT	3+840	750	600											0.5	\$XXX FINE MINIMUM		TSPA	
RT	4+235	750	600			4.9		1	1.8	4.0				0.5	WORK ZONE		TSPA	
RT	4+235	305	610											0.2	BEGINS	12	TSPA	
LT	4+278	600	750											0.5	WORK ZONE		TSPA	
LT	4+278	750	600			4.9		1	1.8	4.0				0.5	SPEED LIMIT 40	9	TSPA	
LT	4+278	305	610											0.2	BEGINS		TSPA	
LT	4+278	450	1000											0.5	\$XXX FINE MINIMUM		TSPA	
MAIN ST. STAGE 3A-2																		
RT	2+363	433	3000	1.3											WEST PEORIA - EAST BLOOMINGTON	25	COVER "PEORIA" WITH "RAMP CLOSED"	
RT	2+375	915	915								1				CLEARANCE 14'-0"		RSPA	
RT	2+464	600	900											0.5	WRONG WAY	27	TSPA	
LT	2+587	433	3000	1.3											EAST BLOOMINGTON - WEST PEORIA	25	COVER "PEORIA" WITH "RAMP CLOSED"	
RT	2+975										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT STA. 2+975	
RT	3+415										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT STA. 3+416	
RT	3+842										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT STA. 3+842	
RT	2+360	425	425	0.2											↻		REMOVE CTSO	
MAIN ST. STAGE 3A-3																		
LT	2+520											1			EAST - I-74 - ←		REINSTALL AT STA. 2+500	
LT	2+605	305	610											0.2	EAST	14	TSPA	
LT	2+605	610	610			4.4		1	1.8	4.0				0.4	I-74		TSPA	
LT	2+605	510	770											0.4	KEEP LEFT		TSPA	
LT	2+605	305	610											0.2	WEST	13	TSPA	
LT	2+605	610	610			4.4		1	1.8	4.0				0.4	I-74		TSPA	
LT	2+605	510	770											0.4	RAMP CLOSED		TSPA	
RT	2+975										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT 2+975	
RT	3+417										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT STA. 3+415	
RT	3+844										1				WORK ZONE - SPEED LIMIT 40 - \$XXX FINE MINIMUM		REINSTALL AT STA. 3+844	
MAIN ST. STAGE 3A-4																		
LT	2+520											1			EAST - I-74 - ←		REINSTALL AT STA. 2+518	
LT	2+600											1			EAST - I-74 - KEEP LEFT		REINSTALL AT STA. 2+605	
LT	2+600											1			WEST - I-74 - RAMP CLOSED		REINSTALL AT STA. 2+605	
SUBTOTAL SHEET 3 OF 5				2.8		** 42.3		** 9			1	10		11.7				

TSPA = TEMPORARY SIGN PANEL ASSEMBLY
 RSPA = REMOVE SIGN PANEL ASSEMBLY

NOTES:
 1. THE REMOVAL OF TEMPORARY SIGNING THAT IS INSTALLED WITHIN THIS CONTRACT IS INCLUDED WITHIN THE RESPECTIVE TEMPORARY SIGNING PAY ITEM.
 2. THE REMOVAL OF TEMPORARY SIGN PANELS OR SIGN PANEL ASSEMBLIES THAT WERE PREVIOUSLY INSTALLED BY OTHERS IS PAID AS "REMOVE SIGN PANEL" OR "REMOVE SIGN PANEL ASSEMBLY" OF THE TYPE SPECIFIED.

△ - ADDED PAY ITEM
 △ - ADDED NOTE

REVISIONS	
NAME	DATE
△ REVISED	MAY 27 2005



T. I. S. SHEET 3 OF 33

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 74 (I-74)
TEMPORARY GUIDE SIGN DETAILS

DRAWN BY RLS
 CHECKED BY JJM

DATE 12-20-04