

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	138-2RS	MCDONOUGH	66	23
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHORT TERM PAVEMENT MARKING (2 LIFTS)

STATION TO STATION	4" WHITE	4" YELLOW
CENTERLINES	FOOT	FOOT
NB STA 61+00 - 141+02.87	728.0	
SB STA 61+00 - 141+02.87	728.0	
TOWER ROAD		20.0
DOG POUND DRIVE		24.0
EDGELINES		
NB RT STA 55+00 - 95+12.60	164.0	
NB RT STA 96+40.39 - 141+02.87	180.0	
NB LT STA 78+82.04 - 84+29.50		28.0
NB LT STA 96+46.37 - 111+89.98		68.0
NBLT STA 112+12.02 - 127+81.93		68.0
NB LT STA 128+06.15 - 133+50.18		28.0
NB LT STA 138+21.06 - 141+02.87		16.0
SB LT STA 56+84 - 70+96.41	60.0	
SB LT STA 73+36.41 - 90+05.30	76.0	
SB LT STA 90+94.38 - 95+00	20.0	
SB LT STA 97+20.72 - 141+02.87	180.0	
SB RT STA 78+82.04 - 84+40.49		28.0
SB RT STA 86+38.45 - 90+26.78		20.0
SB RT STA 90+64.65 - 90+69.86		24.0
SB RT STA 100+95.88 - 111+89.98		48.0
SB RT STA 112+12.02 - 127+81.93		68.0
SB RT STA 128+06.15 - 137+85.35		44.0
SB RT STA 138+21.06 - 141+02.87		16.0
DOG POUND DRIVE	16.0	
MEDIAN		
RT STA 61+00 - 78+31.55		160.0
LT STA 61+00 - 78+31.55		160.0
TURN LANES		
NB STA 77+70.27 - 78+30.27	8.0	
NB STA 88+45.96 - 89+89.96	16.0	
NB STA 93+39.91 - 95+27.98	20.0	
SB STA 96+70.59 - 98+66.16	20.0	
SB STA 97+20.75 - 99+15.48	20.0	
NB STA 135+80.37 - 137+75.37	20.0	
NEW BURLINGTON ROAD	12.0	12.0
SUB-TOTALS	2268.0	832.0
TOTAL (X 2 LIFTS)	6200.0	

TEMPORARY & EPOXY PAVEMENT MARKINGS - LETTERS & SYMBOLS

LOCATION	NO.	SQ FT
LEFT TURN LANES (WHITE)		
STA 77+71.50 - 78+10.50	2	31.2
STA 88+60.53 - 89+60.53	2	31.2
STA 93+73.35 - 94+98.35	2	31.2
STA 97+00.70 - 98+25.70	2	31.2
STA 135+95.40 - 137+4540	2	31.2
RIGHT TURN LANE (WHITE)		
STA 97+50.60 - 98+75.60	2	31.2
DUAL LEFT TURN LANE (YELLOW)		
STA 62+00	2	31.2
STA 64+00	2	31.2
STA 66+00	2	31.2
STA 68+00	2	31.2
STA 70+00	2	31.2
STA 73+00	2	31.2
STA 75+00	2	31.2
NEW BURLINGTON ROAD		
RIGHT TURN (WHITE)	1	15.6
LEFT TURN (WHITE)	1	15.6
TOTALS	28	436.8

TEMPORARY & PREFORMED PLASTIC PAVEMENT MARKING, TY B LINE 6"

SOUTHBOUND	SKIP DASH WHITE (FT)
STA 61+00 - 141+02.87	2000.0
NORTHBOUND	
STA 61+00 - 141+02.87	2000.0
TOTALS	4000.0

TEMPORARY & EPOXY PAVEMENT MARKING LINE 8"

LOCATION	RT TURN LANE WHITE (FT)	LT TURN LANE WHITE (FT)
MEDIAN STA 77+70.27 - 78+30.27		60.0
NB STA 88+45.96 - 89+89.96		144.0
NB STA 93+39.91 - 95+27.98		188.0
SB STA 96+70.59 - 98+66.16		196.0
SB STA 97+20.75 - 99+15.48	195.0	
NB STA 135+80.37 - 137+75.37		195.0
TOTAL	978.0	

TEMPORARY & EPOXY PAVEMENT MARKING LINE 12"

LOCATION	CHEVRONS YELLOW (FT)
MEDIAN STA 76+09.81 - 78+31.55	233.9
NEW BURLINGTON ROAD	64.5
TOTAL	298.4

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	SQ FT
CENTERLINES	507.9
TURN LANE LINES	34.6
MEDIAN	106.7
EDGELINES	383.9
TOTALS	1033.1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLOT DATE: 3/25/2008
 PLOT NAME: 68334A.dwg
 PLOT SCALE: 1/8"=1'-0"
 REFERENCE: *WREF*