

P.A.I. SITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
T4	I72-8H8-21	PEORIA	18	5
STA. 146+204.55		TO STA. 149+904.55		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

MOBILIZATION

JOBSITE = 1.0 LSUM
TRAFFIC CONTROL AND PROTECTION, STD. 701401
 E.B. I-74 WORK AREA = 1.0 EACH
TRAFFIC CONTROL AND PROTECTION, STD. 701402
 SHERIDAN RD. WORK AREA = 1.0 EACH
TRAFFIC CONTROL AND PROTECTION, STD. 701400
 I-74 AND SHERIDAN RD. WORK AREAS = 2.0 EACH
PROTECTIVE SHIELD
 ABOVE E.B. I-74 LANES = 100 SQ.M
TEMPORARY CONCRETE BARRIER
 SHERIDAN RD. DECK = 60 M
PAVEMENT MARKING TAPE, TYPE I 100MM
 SHERIDAN RD. DECK = 60 M
IMPACT ATTENUATOR TEMP. NRD TL2
 JOBSITE = 1 EACH

CONCRETE REMOVAL

S.W. SIDEWALK/PARAPET = 35.5 CU.M
REMOVAL OF EXISTING PPC DECK BEAMS
 S.W. FASCIA BEAM = 1.0 EACH
FURNISH & ERECT PPC I-BEAM, 1372MM
 JOBSITE = 28.6 M
REINFORCEMENT BARS, EPOXY COATED
 JOBSITE = 3300 KG
MECHANICAL SPLICER
 JOBSITE = 292 EACH
CONCRETE SUPERSTRUCTURE
 JOBSITE = 35.5 CU.M
PROTECTIVE COAT
 JOBSITE = 100 SQ.M

PLOT DATE: 03/15/2005
 FILE NAME: S:\CONTRACTS\2004\US-504014\bridge\Revised\US-74-05 RESUBMITTAL\68492 SW72-01193 SheridanBridge.dwg
 PLOT SCALE: 1/8"=1'-0"
 REFERENCE: WSP

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY: CEJ
 HORIZ. CHECKED BY:
 DATE: 03-15-2005