

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	105BR	CHAMPAIGN	36	4

CONTRACT NO. 70391

LOCATION OF WORK: FAP 709  
2112+00  
TO  
2114+50  
80% FEDERAL  
20% STATE  
RURAL TWO LANE

CONSTRUCTION TYPE CODE: X028-2A  
TOTAL  
QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	275.0
20900110	POROUS GRANULAR BACKFILL	CU YD	288.0
25000200	SEEDING, CLASS 2	ACRE	1.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90.0
25100115	MULCH, METHOD 2	ACRE	1.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100.0
28000300	TEMPORARY DITCH CHECKS	EACH	8.0
28000400	PERIMETER EROSION BARRIER	FOOT	400.0
28000500	INLET AND PIPE PROTECTION	EACH	5.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	97.0
28200200	FILTER FABRIC	SQ YD	97.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	9.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	37.0
40600990	TEMPORARY RAMP	SQ YD	55.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1.0
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	723.0
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ YD	19.0
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	174.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	20.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
51500100	NAME PLATES	EACH	1.0