

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	1058R	CHAMPAIGN	36	5

LOCATION OF WORK: FAP 709
2112+00
TO
2114+50
80% FEDERAL
20% STATE

CONTRACT NO. 70391

RURAL TWO LANE
CONSTRUCTION TYPE CODE: X028-2A
TOTAL
QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
54001000	BOX CULVERT END SECTIONS	EACH	2.0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	120.0
54021111	PRECAST CONCRETE BOX CULVERT 11' X 11' (M273)	FOOT	88.0
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	487.5
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50.0
*63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4.0
63200310	GUARDRAIL REMOVAL	FOOT	587.5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	563.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	563.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4.0
*78200405	GUARDRAIL MARKERS	EACH	7.0
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4.0
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	563.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	63.0
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	41.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	42.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0
* SPECIALITY ITEMS			