

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	143I-1	DOUGLAS	67	4

CONTRACT NO. T0466

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	LOCATION OF WORK:
					DOUGLAS COUNTY RURAL FAP 323 STA. 9+88.90 STA.35+65 100% STATE SFTY-2A
20200100	EARTH EXCAVATION		CU YD	488.0	488.0
20400800	FURNISHED EXCAVATION		CU YD	210.0	210.0
25000210	SEEDING, CLASS 2A		ACRE	0.9	0.9
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	78.0	78.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	78.0	78.0
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	78.0	78.0
25100115	MULCH, METHOD 2		ACRE	0.9	0.9
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	87.0	87.0
28000300	TEMPORARY DITCH CHECKS		EACH	4.0	4.0
28000400	PERIMETER EROSION BARRIER		FOOT	2,170.0	2,170.0
28000500	INLET AND PIPE PROTECTION		EACH	6.0	6.0
35101400	AGGREGATE BASE COURSE, TYPE B		TON	14.0	14.0
40200800	AGGREGATE SURFACE COURSE, TYPE B		TON	30.0	30.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	380.0	380.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	38.0	38.0
40800030	AGGREGATE (PRIME COAT)		TON	1.0	1.0
40800040	INCIDENTAL BITUMINOUS SURFACING		TON	18.0	18.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"		SQ YD	96.0	96.0
44000200	DRIVEWAY PAVEMENT REMOVAL		SQ YD	77.0	77.0
44004250	PAVED SHOULDER REMOVAL		SQ YD	1,732.0	1,732.0
48202210	BITUMINOUS SHOULDERS SUPERPAVE 4 1/2"		SQ YD	3,744.0	3,744.0
50105220	PIPE CULVERT REMOVAL		FOOT	37.0	37.0
54213453	END SECTIONS 18"		EACH	2.0	2.0
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"		FOOT	36.0	36.0
67100100	MOBILIZATION		L SUM	1.0	1.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	195.0	195.0
* 70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"		FOOT	4,208.0	4,208.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	65.0	65.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	4,208.0	4,208.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50		TON	315.0	315.0
	* SPECIALITY ITEM				