

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1678	6 MFT. Q	EDGAR	29	8

CONTRACT NO. 70467

**SCHEDULE OF QUANTITIES**

78001180 - PAINT PAVEMENT MARKING - LINE 4"

\*NO EDGE LINES

YELLOW:

SKIP-DASH LINES = 2,632 FEET

SOLID LINES = 640 FEET

NO PASSING ZONES

NB STA. 19+95 TO STA. 23+15

SB STA. 23+25 TO STA. 26+45

TOTAL QUANTITY = 3,272 FEET

XX000125 - AGGREGATE BASE COURSE TYPE B SPECIAL

SIDERoads:

STA. 18+50.0 RT. (2240N) = 9.18 TONS  
 STA. 24+15.0 RT. (2256N) = 9.18 TONS  
 STA. 31+67.0 RT. (2263N) = 9.18 TONS  
 STA. 37+47.0 RT. (2275N) = 9.18 TONS  
 STA. 52+49.8 RT. (2308N) = 9.18 TONS  
 STA. 52+49.8 LT. (2308N) = 9.18 TONS

TOTAL = 55.10 TONSPRIVATE ENTRANCES:

STA. 6+52 LT. = 0.06 TON  
 STA. 7+50 RT. = 0.06 TON  
 STA. 15+96 RT. = 0.06 TON  
 STA. 19+52 RT. = 0.06 TON  
 STA. 25+85 LT. = 0.06 TON  
 STA. 25+99 RT. = 0.06 TON  
 STA. 30+92 RT. = 0.06 TON  
 STA. 33+44 RT. = 0.06 TON  
 STA. 35+74 RT. = 0.06 TON  
 STA. 39+11 RT. = 0.06 TON  
 STA. 39+55 LT. = 0.06 TON  
 STA. 72+79 RT. = 0.06 TON

TOTAL = 0.70 TONSMAILBOX TURNOUTS:

STA. 11+31 LT. = 0.06 TON  
 STA. 16+35 LT. = 0.06 TON  
 STA. 18+80 LT. = 0.06 TON  
 STA. 25+85 LT. = 0.06 TON  
 STA. 31+66 LT. = 0.06 TON  
 STA. 36+07 LT. = 0.06 TON  
 STA. 72+79 RT. = 0.06 TON

TOTAL = 0.40 TONSGRAND TOTALS = 57.00 TONS