

SUMMARY OF QUANTITIES

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------|---------|-----------|--------------|-----------|
| * | ** | CHAMPAIGN | 21 | 3 |

CONTRACT NO. 70470
 * F.A.P. RTE. 836 & F.A.S. RTE. 516
 ** D-5 CONTRACT MAINT 2005-13

LOCATION OF WORK:

LOCATION #1 - Ogden
 FAP 836
 STA. 326+54.00
 TO
 STA. 338+99.0
 100% STATE
 TWO-LANE RURAL
 1000

LOCATION #2 - St. Joseph
 FAS 516
 STA. 29+32.00
 TO
 STA. 66+32.00
 100% STATE
 TWO-LANE RURAL
 1000

CONSTRUCTION TYPE CODE:

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | QUANTITY | QUANTITY |
|------------|---|--------|----------------|----------|----------|
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 620.0 | 152.0 | 468.0 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 25.0 | 6.0 | 19.0 |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 400.0 | 0.0 | 400.0 |
| 40600990 | TEMPORARY RAMP | SQ YD | 440.0 | 147.0 | 293.0 |
| 40800010 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 156.5 | 116.5 | 40.0 |
| 40800030 | AGGREGATE (PRIME COAT) | TON | 3.0 | 2.0 | 1.0 |
| 40800040 | INCIDENTAL BITUMINOUS SURFACING | TON | 132.0 | 98.0 | 34.0 |
| 44000006 | BITUMINOUS SURFACE REMOVAL 1 1/2 | SQ YD | 11,071.0 | 3043.0 | 8028.0 |
| 44000025 | BITUMINOUS SURFACE REMOVAL (SPECIAL) | SQ YD | 1,165.0 | 1165.0 | 0.0 |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 117.8 | 0.0 | 117.8 |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 63.5 | 63.5 | 0.0 |
| 44201789 | CLASS D PATCHES, TYPE II, 12 INCH | SQ YD | 160.0 | 0.0 | 160.0 |
| 44201803 | CLASS D PATCHES, TYPE II, 13 INCH | SQ YD | 40.0 | 0.0 | 40.0 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B" | TON | 113.0 | 20.0 | 93.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 | 0.5 | 0.5 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1.0 | 0.5 | 0.5 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 1,426.0 | 249.0 | 1177.0 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 238.0 | 83.0 | 155.0 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4 | FOOT | 9,760.0 | 2801.0 | 6959.0 |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4 | FOOT | 6,333.0 | 0.0 | 6333.0 |
| * 88600100 | DETECTOR LOOP, TYPE I | FOOT | 106.0 | 106.0 | 0.0 |
| X4066424 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX ""D"", N50 | TON | 1,041.0 | 256.0 | 785.0 |

* SPECIALTY ITEMS