

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		MACOUPIN	79	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* 10Z (RS-1); (V,T) RS-2; SRS-4)

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION						
					URBAN	URBAN	URBAN
						Y025	5F74-1B
				RURAL ROADWAY 1000 80% FED 20% STATE	CITY ROADWAY 1000 80% FED 20% STATE	CITY PARKING LANES 50% STATE 50% CITY	CITY C & G AND S. W. 100% CITY
28001000	AGGREGATE EROSION CONTROL	TON	40	40	-	-	-
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	270	270	-	-	-
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	300	300	-	-	-
28200200	FILTER FABRIC	SQ YD	540	540	-	-	-
35800100	PREPARATION OF BASE	SQ YD	2,320	1,910	410	-	-
35800200	AGGREGATE BASE REPAIR	TON	64	57	7	-	-
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	100	92	8	-	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	64	55	8	1.0	-
40600300	AGGREGATE (PRIME COAT)	TON	332.8	286.4	41.0	5.4	-
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	-	-	-
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,276	1,461	815	-	-
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	573	460	113	-	-
40600990	TEMPORARY RAMP	SQ YD	314	79	235	-	-
40800020	BITUMINOUS MATERIAL (PRIME COAT)	TON	1.8	1.3	0.5	-	-
40800030	AGGREGATE (PRIME COAT)	TON	10	7	3	-	-

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 662
 SECTION IV, TIR-2; S-RS-3; B-2
 MACOUPIN COUNTY
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

PLOT DATE = 2/21/2008
 FILE NAME = C:\pwork\72405\662\summary.dgn
 PLOT SCALE = 1/8"=1'-0"
 REFERENCE = REF