CONTRACT NO. 72405

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	74	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 10Z (RS-1); (V,T) RS-2; S(RS-4)

SUMMARY OF QUANTITIES

PAY CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
					URBAN	URBAN Y025	URBAN SFTY-1B
				RURAL ROADWAY 1000 80% FED 20% STATE	CITY ROADWAY 1000 80% FED 20% STATE	CITY PARKING LANES 50% STATE 50% CITY	CITY C &G AND S. W. 100% CITY
44000006	BITUMINOUS SURFACE REMOVAL - 1 1/2"	SQ YD	15,935	-	13,215	2,720	-
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	79,944	79,944	-	-	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	101	39	62	-	-
44000400	GUTTER REMOVAL	FOOT	3,435	2,686	749	-	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,295	1,295	-	-	-
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	207	-	157	-	50
44002600	GUTTER OUTLET REMOVAL	FOOT	530	51	479	-	-
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	2,000	-	2,000	-	-
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	409	409	-	-	-
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	763	763	-	-	-
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	1,518	1,518	-	-	-
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	114	114	-	-	-
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	17	17	-	-	-

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP 662
SECTION (V, T)R-2; S-RS-3; B-2
MACOUPIN COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 3/31/2005
FILE NAME = c:\projects\d662202\summary.dgn
PLOT SCALE = 188.4337 ' / IN.
REFERENCE = WSF