

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		MACQUEIN	74	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• 10Z (RS-1); (V,T) RS-2; S(RS-4)

BITUMINOUS WIDENING / SHOULDERS & AGGREGATE SHOULDERS

LOCATION	LENGTH	BIT PAY WIDTH	BITUMINOUS SHOULDERS SUPER., 8"	BIT. CONC. BSE. CSE. WID. SUPER., 10"	EXCAVATING AND GRADING EX SHLDS	GRADING AND SHAPING SHOULDERS	EARTH EXCAVATION (WIDENING)	AGG WIDTH	AGGREGATE SHOULDERS	AGGREGATE SHOULDERS (SPECIAL)	REMOVE & REINSTALL SPBGR
	FOOT	FOOT	SO YD	SO YD	UNIT	UNIT	UNIT	FOOT	TON	TON	FOOT
RT STA 245+15.00 TO RT STA 245+65.00	50.00	3.0 TO 1.0	11.1	-	0.50	-	-	3.0	2.37	-	-
RT STA 245+65.00 TO RT STA 442+67.00	19702.00	1.2	2626.9	-	197.02	-	-	3.0	934.93	-	-
RT STA 442+67.00 TO RT STA 446+16.20	349.20	5.2	-	201.8	-	-	3.49	-	-	-	-
RT STA 446+16.20 TO RT STA 447+91.40 - BRIDGE OMISSION											
RT STA 447+91.40 TO RT STA 450+65.00	273.60	5.2	-	158.1	-	-	2.74	-	-	-	-
RT STA 450+65.00 TO RT STA 450+74.00	9.00	5.2 TO 1.2	-	3.2	-	-	0.09	-	-	-	-
RT STA 450+74.00 TO RT STA 478+00.00 (BK)	2726.00	1.2	363.5	-	27.26	-	-	3.0	129.36	-	-
PART "B" - RURAL											
LT STA 38+00.00 TO LT STA 143+20.00	10520.00	1.2	1402.7	-	105.20	-	-	3.0	499.21	-	-
LT STA 143+20.00 TO LT STA 157+70.00	1450.00	-	-	-	-	-	-	3.0	68.81	-	-
LT STA 157+70.00 TO LT STA 201+90.00	4420.00	1.2	589.3	-	44.20	-	-	3.0	209.75	-	-
LT STA 201+90.00 TO LT STA 202+00.00 - RAILROAD OMISSION											
LT STA 202+00.00 TO LT STA 246+16.00	4386.00	1.2	584.8	-	43.86	-	-	3.0	208.13	-	-
LT STA 246+16.00 TO LT STA 259+79.19 (BK)	1363.19	-	-	-	-	-	-	3.0	64.69	-	-
RT STA 38+00.00 TO RT STA 143+20.00	10520.00	1.2	1402.7	-	105.20	-	-	3.0	499.21	-	-
RT STA 143+20.00 TO RT STA 157+70.00	1450.00	-	-	-	-	-	-	3.0	68.81	-	-
RT STA 157+70.00 TO RT STA 201+90.00	4420.00	1.2	589.3	-	44.20	-	-	3.0	209.75	-	-
RT STA 201+90.00 TO RT STA 202+00.00 - RAILROAD OMISSION											
RT STA 202+00.00 TO RT STA 246+16.00	4386.00	1.2	584.8	-	43.86	-	-	3.0	208.13	-	-
RT STA 246+16.00 TO RT STA 259+79.19 (BK)	1363.19	-	-	-	-	-	-	3.0	64.69	-	-
SIDERoads (SEE SEPARATE SIDERoad SCHEDULE)	-	-	575.6	-	13.00	-	1.00	-	-	-	-
SUB-TOTAL =			14,892.6	729.7	1,016.85	-	13.76	-	4,886.90	19.58	-
TOTAL =			16,769.9	729.7	1,072.2	6.4	13.8	-	5,160.1	19.6	640.0

NOTE: SHOULDERS SHALL NOT CONTINUE THROUGH SIDE ROADS. THIS SCHEDULE DOES NOT INCLUDE THESE ESTIMATED DEDUCTIONS FOR FINAL MEASURED QUANTITIES DUE TO LACK OF SURVEY INFORMATION.

PIPE / BOX CULVERTS

LOCATION	CONCRETE COLLAR	PIPE CULV TY-1, CS/A 18"	PIPE CULV TY-1, CS/A 24"	METAL END SECTIONS 18"	METAL END SECTIONS 24"	CONCRETE REMOVAL	CONC HDWL REMOVAL	STONE DUMPED RIPRAP, CL B3	STONE DUMPED RIPRAP, CL A4	FILTER FABRIC FOR RIPRAP
	EACH	FOOT	FOOT	EACH	EACH	CU YD	EACH	TON	TON	SO YD
PART "A" - RURAL										
RT STA 264+74.00 (SIDE ROAD WIDENING)	2	40	-	2	-	-	-	-	-	-
RT STA 282+02.60 (EROSION REPAIR)	-	-	80	-	2	-	1	-	45	90
LT STA 282+02.60 (EROSION REPAIR)	-	-	-	-	-	0.95	-	-	25	50
PART "A" & "B" - RURAL										
EST. QUANTITIES (LOCATIONS DETERMINED BY ENGINEER)	6	100	100	6	6	-	2	300	200	400
TOTAL =	8	140	180	8	8	0.95	3	300	270	540

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY