

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	BROWN	89	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* D6 WETLAND MITIGATION NO. 1				
** LA GRANGE WETLAND BANK				

PIPE CULVERT SCHEDULE				
LOCATION	PIPE CULV	PIPE CULV	METAL	DELIN.
	T-1, CS/A	T-2, CS/A	END SEC	S - WHITE
	18"	18"	18"	CRYSTAL
	(FOOT)	(FOOT)	(EACH)	(EACH)
<u>PR EARTH EMBANKMENT FOR FUTURE ACCESS ROAD</u>				
STA 75+50	72		4	2
STA 90+00	80		4	2
STA 101+80		104	4	2
STA 110+00		112	4	2
TOTAL =	152	216	16	8

FIELD TILE DEACTIVATION SCHEDULE			
LOCATION	EXPLOR.	PLUG	F. T.
	TRENCH	EXISTING	DECTIV.
	52" DEPTH	DRAINS	& REM.
	(FOOT)	(EACH)	(FOOT)
<u>ESTIMATED QUANTITIES @ ESTIMATED LOCATIONS</u>			
<u>FIELD # 1</u>			
RT STA 3017+00 TO RT STA 3050+00	3300	16.5	825
RT STA 702+00 TO RT STA 710+00	800	4	200
<u>FIELD # 2</u>			
LT STA 234+00 TO LT STA 237+00	300	1.5	75
<u>FIELD # 6</u>			
LT STA 73+00 TO LT STA 77+00	400	2	100
<u>FIELD # 7</u>			
LT STA 431+00 TO LT STA 437+00	600	3	150
LT STA 601+00 TO LT STA 613+00	1200	6	300
<u>FIELD # 8</u>			
LT STA 431+00 TO LT STA 450+00	1900	9.5	475
LT STA 601+00 TO LT STA 613+00	1200	6	300
LT STA 3037+00 TO LT STA 3050+00	1300	6.5	325
<u>FIELD # 9</u>			
LT STA 3013+00 TO LT STA 3037+00	2400	12	600
LT STA 316+00 TO LT STA 326+00	1000	5	250
VARIOUS LOCATION IN VARIOUS FIELDS (AS DIRECTED BY THE ENGINEER)	3000	15	750
TOTAL =	17400	72	3600

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY BOK
CHECKED BY JCN

PLOT DATE = 2/9/2005
FILE NAME = c:\projects\72939\72939.dgn
REFERENCE = REF 4