

steffenmk
10/26/2004
c:\projects\74048d\02904pe.dgn



FAP EST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	*	JEFFERSON	11	3

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT NO.
CONTRACT NO. 74048
• (13-2)RS-2,13ZRS-3

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		I 000-2A		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4865	4865		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	590	590		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	48652	48652		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10	10		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,370	10,370		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1730	1730		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	982.8	982.8		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18650	18650		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3250	3250		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	620	620		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	490	490		
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3260	3260		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	530	530		
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	170	170		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1960	1960		
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	3406	3406		

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY: