

SUMMARY OF QUANTITIES

MAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
600	51RS-3	*	347	7A
STA.		TO STA.		
CONTRACT : 76563				
* ST. CLAIR & MONROE COUNTIES				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000-2A 100% STATE ST. CLAIR COUNTY	1000-2A 100% STATE MONROE COUNTY	X028-2A 100% STATE ST. CLAIR COUNTY	Y007 100% STATE ST. CLAIR COUNTY	Y025 50% STATE 50% VILLAGE ST. CLAIR COUNTY	Y025 50% STATE 50% VILLAGE MONROE COUNTY	SFTY-3N 100% STATE ST. CLAIR COUNTY	SFTY-2A 100% STATE ST. CLAIR COUNTY
MX033228	GRATE FOR PRECAST CONCRETE BOX CULVERT END SECTION 0.9M X 0.6M	EACH	6	6							
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	2166						2166		
MX355230	BITUMINOUS BASE COURSE SUPERPAVE, 230MM	SQ M	3769	2379		627	763				
MX406024	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	M TON	7392	6590.8	771						30.2
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	3565	3190.5	365						9.5
MX482330	BITUMINOUS SHOULDERS SUPERPAVE 200MM	SQ M	29857	29135	722						
MX540100	PRECAST CONCRETE BOX CULVERT 1.5M X 0.6M (M273)	METER	1.2	1.2							
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4			2	2				
X7200200	WIDE LOAD SIGNING	L SUM	1	1							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4							4	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4							4	
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	4	4							
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1			1					

5/4/2005 8:55:48 AM
C:\p3p3\p3\work\76563\summary.dgn L:\1-63

Rai