

SUMMARY OF QUANTITIES

F&P NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	138BR-2,138BR-3	BOND	26	3
STA.		TO STA.		
CONTRACT NO.: 76860				

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		S.N. 003-0024		S.N. 003-0025	
				BRIDGE BIG SHOAL CREEK X080-2A	RDWY BIG SHOAL CREEK X080-2A	BRIDGE INDIAN CREEK X080-2A	RDWY INDIAN CREEK X080-2A
25000210	SEEDING, CLASS 2A	ACRE	1	0.5		0.5	
X0324952	DETOUR SIGNING	L SUM	1	0.5		0.5	
25100105	MULCH, METHOD 1	ACRE	1	0.5		0.5	
20400800	FURNISHED EXCAVATION	CU YD	200	100		100	
28000250	TEMPORARY EROSION CONTROL SEEDING	POLYAD	200	100		100	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0		0.5		0.5
40600300	AGGREGATE (PRIME COAT)	TON	2.0		1.0		1.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1223		629		594
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	440	220		220	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	88	44		44	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	14	7		7	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	4		4		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1		1	
50104000	BRIDGE RAIL REMOVAL	FOOT	502	367		135	
50300225	CONCRETE STRUCTURES	CU YD	8.2	4.7		3.5	
50300260	BRIDGE DECK GROOVING	SQ YD	1697	1246		451	
50300300	PROTECTIVE COAT	SQ YD	2367	1609		758	
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	571	420		151	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	16298	11969		4329	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	22420	16350		6070	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	1003	734		269	
51500100	NAME PLATES	EACH	2	1		1	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8		4		4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6		2		4
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	755		355		400
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	2.5		2.5	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	920		460		460
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1054	744		310	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4		2		2
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	7	5		2	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	16		16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	2		3	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12		6		6
X0320887	POLYMER CONCRETE	CU FT	7.2	7.2			
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	33	33			
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	33	33			
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	33		16		17
X4066612	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N30	TON	22		11		11
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	1721	1264		457	
XX004814	SILICONE JOINT SEALER, 3"	FOOT	33	33			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	88	88			
T0101830	TRAFFIC CONTROL AND PROTECTION, B&R-21	L SUM	1	0.5		0.5	

* SPECIALTY ITEMS

Rev.