F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	55
STA. 10+70.70	TO STA. 66+16.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83781

PLAN — SURVEYED / PLOTTED / CROSS SECTIONS CHECKED / ALIGNMENT NOTES CHECKED / NOTE BOOK NO. ____ / CADD FILE NAME ____ — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / STRUCTURE NOTATNS. CHKD — BY — DATE

PIPE TABLE

PIPE NO.	STATION	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)
185	36+30.00	36+85.00	CL A TY 2	29x45	55.0	37.35
187	36+85.00	36+85.00	CL A TY 2	24x38	16.8	8.10
189	39+04.74	36+85.00	CL A TY 2	24x38	219.7	17.70
193	40+30.00	39+04.74	CL A TY 2	24x38	125.3	53.06
195	41+15.00	40+30.00	CL A TY 2	34x53	85.0	77.05
231	43+40.00	43+50.00	SS (WM REQ)	12	20.6	15.00
233	44+40.00	44+40.00	SS (WM REQ)	12	32.2	10.98
235	44+80.00	44+80.00	CL A TY 2	12	18.0	5.00
236	44+80.00	44+80.00	CL A TY 2	12	6.0	3.98
237	45+60.00	45+60.00	SS (WM REQ)	12	32.2	10.30
238	45+00.00	44+80.00	CL A TY 2	12	26.0	19.77
239	47+10.00	47+10.00	SS (WM REQ)	12	18.0	5.00
240	46+60.00	46+60.00	CL A TY 2	12	22.7	7.74
241	46+30.00	46+30.00	SS (WM REQ)	12	32.2	10.64
242	47+10.00	47+10.00	CL A TY 2	12	6.0	1.61
243	48+90.00	48+80.00	SS (WM REQ)	12	14.9	9.89
244	48+75.00	48+80.00	CL A TY 2	12	17.4	12.39
245	48+80.00	48+80.00	CL A TY 2	12	21.2	6.78
246	48+80.00	48+80.00	CL A TY 2	12	6.0	2.24
247	49+50.00	49+50.00	CL A TY 2	24	23.2	5.45
248	49+50.00	49+50.00	CL A TY 1	24	22.7	7.00
249	50+10.00	50+10.00	CL A TY 1	24	24.9	4.00
250	50+10.00	50+10.00	CL A TY 1	24	6.3	1.10
252	50+65.00	50+65.00	CL A TY 1	21	8.0	1.33
253	50+65.00	50+65.00	CL A TY 1	21	30.4	4.20
256	51+50.00	51+50.00	CL A TY 1	18	10.7	1.52
257	51+07.50	51+90.00	SS (WM REQ)	12	82.6	15.16
258	50+50.00	50+65.00	CL A TY 1	12	21.4	6.85
290	43+50.00	44+80.00	CL A TY 2	12	130.0	121.71
294	44+80.00	47+10.00	CL A TY 2	12	230.0	160.08
298	47+10.00	48+80.00	CL A TY 2	43x68	170.0	300.56
300	48+80.00	49+00.00	CL A TY 2	38x60	20.0	12.24
302	49+50.00	50+10.00	CL A TY 1	24x38	60.0	15.99
304	50+10.00	50+65.00	CL A TY 1	22x34	55.0	11.25
306	50+65.00	51+50.00	CL A TY 1	19x30	85.0	16.45
308	51+50.00	51+65.00	CL A TY 1	19x30	15.0	2.66
310	51+65.00	51+95.00	CL A TY 1	15	32.2	4.99
312	51+95.00	52+01.50	CL A TY 1	15	7.4	0.98
314	49+00.00	49+50.00	CL A TY 2	29x45	50.0	15.80
351	52+90.00	53+03.36	SS (WM REQ)	12	20.9	4.27

PIPE TABLE

PIPE NO.	STATION	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)
352	52+50.00	52+39.40	CL A TY 2	12	10.0	3.20
354	53+35.00	53+35.00	CL A TY 2	12	6.3	1.82
355	53+70.00	53+70.00	SS (WM REQ)	12	15.9	3.08
356	57+60.00	57+55.00	CL A TY 2	12	5.0	1.60
358	54+15.00	54+15.00	CL A TY 2	12	8.4	2.34
360	55+10.00	55+10.00	CL A TY 2	12	7.0	2.02
362	55+75.00	55+75.00	CL A TY 2	12	7.0	1.95
363	54+75.00	54+75.00	CL A TY 2	12	12.0	3.34
364	56+50.00	56+60.00	CL A TY 2	12	5.0	1.76
365	55+25.00	55+25.00	CL A TY 2	12	9.9	2.65
366	56+60.00	56+60.00	CL A TY 2	12	7.0	2.02
367	55+80.00	55+80.00	CL A TY 2	12	7.6	2.03
368	57+10.00	57+10.00	CL A TY 2	12	7.0	1.95
369	56+35.00	56+35.00	CL A TY 2	12	7.3	1.95
370	57+55.00	57+55.00	CL A TY 2	12	7.0	1.95
371	57+30.00	57+29.59	CL A TY 2	12	4.7	1.21
372	58+41.00	58+41.00	CL A TY 2	12	7.0	2.02
375	58+00.00	58+00.00	CL A TY 2	12	4.5	1.16
376	59+00.00	58+90.00	CL A TY 2	12	12.0	3.46
377	58+54.00	58+54.00	CL A TY 2	12	5.0	1.34
378	60+05.00	60+05.00	CL A TY 2	12	4.5	1.20
379	59+00.00	59+00.00	CL A TY 2	12	6.2	1.66
380	61+35.00	61+00.00	CL A TY 2	12	30.0	9.60
381	59+50.00	59+50.00	CL A TY 2	12	7.5	2.01
382	60+05.00	60+05.00	CL A TY 2	12	12.0	6.09
383	60+05.00	60+05.97	CL A TY 2	12	9.0	2.41
384	63+09.00	63+15.83	SS (WM REQ)	12	28.8	3.56
385	60+90.00	60+90.00	CL A TY 2	12	6.1	1.63
386	63+59.00	63+50.18	CL A TY 1	12	16.1	2.10
389	63+15.00	63+15.00	CL A TY 2	12	17.9	5.35
393	63+64.09	63+51.06	CL A TY 1	12	13.3	1.76
450	53+35.00	53+00.00	CL A TY 2	42	35.0	19.46
454	55+10.00	53+35.00	CL A TY 2	42	175.0	106.75
458	56+60.00	55+10.00	CL A TY 2	48	150.0	101.25
464	58+41.00	56+60.00	CL A TY 2	54	181.0	156.85
468	58+90.00	58+41.00	CL A TY 2	48	49.0	62.92
470	60+05.00	58+90.00	CL A TY 2	12	115.0	91.11
474	61+00.00	60+05.00	CL A TY 2	12	95.0	61.56

REVISIONS NAME	DATE

Stanley Consultants INC.
850 West Higgins Road
Suite 730
Chicago, Illinois 60631-2801 Illinois Firm Registration No.: 184-001533

VILLAGE OF VILLA PARK, ILLINOIS

PIPE TABLE
SOUTH VILLA AVENUE
SHEET 2 OF 2

SCALE: NONE — DRAWN BY: E.D.
DATE: 11-NOV-2004 — CHECKED BY: J.T.G.

O:\5367\Phase2\07-Design\05-Dwgs\sht\367cdrsh2.dgn
11-NOV-2004