

SUMMARY OF QUANTITIES					
CODE	PAY ITEM	UNIT	TOTAL QTY.	H23	O7C
				I000	I000 100% Village
20800150	TRENCH BACKFILL	CUYD	360	60	300
* 21101615	TOPSOIL FURNISH AND PLACE, 4 INCH	SQYD	400	100	300
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3	
* 25200100	SODDING	SQYD	400	100	300
* 25200200	SUPPLEMENTAL WATERING	UNIT	3	3	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,710	4,710	
40600300	AGGREGATE (PRIME COAT)	TON	95	95	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQYD	300	300	
42101300	PROTECTIVE COAT	SQYD	250	250	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	85	85	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQFT	650	650	
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQYD	23,500	23,500	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	85	85	
44000600	SIDEWALK REMOVAL	SQFT	650	650	
44001700	COMBINATION CONCRETE CURB AND GUTTER, REMOVAL AND REPLACEMENT	FOOT	725	725	
44200934	CLASS B PATCHES, TYPE II, 8"	SQYD	20		20
44200944	CLASS B PATCHES, TYPE IV, 8"	SQYD	100		100
44201353	CLASS C PATCHES, TYPE II, 10"	SQYD	50	50	
44201357	CLASS C PATCHES, TYPE III, 10"	SQYD	60	60	
44201359	CLASS C PATCHES, TYPE IV, 10"	SQYD	540	300	240
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	100		100
56103100	DUCTILE IRON WATER MAIN 8"	FOOT	350		350
56103300	DUCTILE IRON WATER MAIN 12"	FOOT	20		20
56400820	FIRE HYDRANT WITH AUXILLIARY VALVE AND BOX	EACH	1		1
60228110	MANHOLE, SANITARY, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60248700	VALVE VAULTS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2
60248900	VALVE VAULTS, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6		6
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	7	7	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	29	29	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	46	46	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	7	7	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	
60500405	FILLING VALVE VAULTS	EACH	13		13

\* DENOTES SPECIALITY ITEM

SUMMARY OF QUANTITIES					
CODE	PAY ITEM	UNIT	TOTAL QTY.	H23	O7C
				I000	I000 100% Village
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	275	275	
* 70300625	TEMPORARY PAINT PAVEMENT MARKING, LINE 4"	FOOT	1,900	1,900	
* 70300660	TEMPORARY PAINT PAVEMENT MARKING, LINE 24"	FOOT	40	40	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,500	9,500	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,000	2,000	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	375	375	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	65	65	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	60	60	
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE D, N50	TON	2,600	2,600	
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1,050	1,050	
X7015000	CHANGEABLE MESSAGE SIGN	CAL-MO	3	3	
XX001490	GATE VALVES, 8"	EACH	2		2
XX003032	GATE VALVES, 12"	EACH	1		1
XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	3,000		3,000
XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	30	10	20
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20	
Z0019600	DUST CONTROL WATERING	UNIT	25	25	
Z0045002	PRESSURE CONNECTION 12" X 8"	EACH	5		5
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0056800	SANITARY SEWER 6"	FOOT	15	15	
Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	40	40	
XX005535	Sewer Spot Repairs, 12"	FOOT	51	51	
XX005634	12" X 6" SEWER SERVICE CONNECTIONS	EACH	3	3	
XX006227	RESTRAINED JOINT, 8"	EACH	10		10
XX006228	RESTRAINED JOINT, 6"	EACH	6		6
XX006196	SHORT WATER SERVICE	EACH	10		10
XX006200	CONNECTION AT ARTHUR AVENUE AND LINCOLN AVENUE	EACH	1		1
XX006201	CONNECTION AT MADISON AVENUE AND LINCOLN AVENUE	EACH	1		1
XX006202	WATER MAIN DISCONNECTION	EACH	3		3
XX006216	Portland Cement Concrete Sidewalk 5 inch (Ramp)	SQFT	40	40	

\* DENOTES SPECIALITY ITEM