

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	***	FULTON	684	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*** 181,(18BRY&18BRY-1)BR,18B-1				

# SCHEDULE OF QUANTITIES

CONCRETE MEDIAN TYPE SM 4.24	
LOCATION	SQ FT
US 24/US 136	
US 24/ US 136 N INTERSECTION	118.24
<b>TOTAL</b>	<b>118</b>

TEMPORARY BRIDGE COMPLETE	
LOCATION	EACH
STAGE I - US 24 SPOON RIVER TRIBUTARY STA 84+00 TO 84+41	1
<b>TOTAL</b>	<b>1</b>

INCIDENTAL BITUMINOUS SURFACING	
LOCATION	TON
STAGE I - US 24/US 136 INTERSECTION TEMPORARY ISLAND	2
PERSONAL ENTERANCE - US 24 STA 26+16.62	31
<b>TOTAL</b>	<b>33</b>

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
LOCATION	YELLOW DIAGONAL	WHITE DIAGONAL
	FOOT	FOOT
US 24/ US 136 N ISLAND AND MEDIANS	207	27
<b>TOTAL</b>	<b>234</b>	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
LOCATION	EACH
US 24 JOBSITE	135
<b>TOTAL</b>	<b>135</b>

PAVEMENT MARKING REMOVAL				
LOCATION	DISTANCE	YELLOW LINES	WHITE LINES	FOOT
	FOOT			
STAGE IA 71+50 TO 78+50	700	2	2	2800
STAGE IIA 3+80 TO 12+50	870	2	2	3480
96+00 TO 113+00	1700	2	2	6800
AFTER STAGE IIB 95+00 TO 96+00	100	2	2	400
STAGE III 78+00 TO 82+50	450		1	450
86+00 TO 90+43	443		1	443
88+31.50 TO 90+43	212	2		423
STAGE IV 67+60 TO 68+35	75		2	150
<b>TOTAL</b>				<b>14,946</b>

BITUMINOUS CONCRETE BASE COURSE WIDENING 10"	
LOCATION	SQ YD
US 24 NW CORNER OF US 24/136 INT	105
<b>TOTAL</b>	<b>105</b>

TEMPORARY PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
US 24/ US 136 N PERIMETER OF TEMPORARY ISLAND	66
<b>TOTAL</b>	<b>66</b>

THERMOPLASTIC PAVEMENT MARKING - LINE 24"	
LOCATION	FOOT
US 24/US 136 N LT TURN FROM US 136 N RT TURN FROM US 136 N	12 16
<b>TOTAL</b>	<b>28</b>

LOCATION	SEEDING CLASS 2A*	MULCH METHOD 2	NITROGEN FERTILIZER NUTRIENTS	PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS
	ACRES	ACRES	LBS	LBS	LBS
US 24					
STA 0+00 to 30+00	3.49	3.49	314.21	314.21	314.21
STA 30+00 TO 64+00	11.93	11.93	1073.68	1073.68	1073.68
STA 65+44 TO 70+51	3.13	3.13	281.40	281.40	281.40
STA 77+70 TO 82+60	0.52	0.52	47.06	47.06	47.06
STA 82+60 TO 85+26	0.23	0.23	21.11	21.11	21.11
STA 85+26 TO 113+00	6.24	6.24	561.79	561.79	561.79
STA 113+00 TO 132+00	2.59	2.59	232.82	232.82	232.82
LIDWELL STA 0+25 TO 2+00	0.17	0.17	15.36	15.36	15.36
HAZLANE STA 0+00 TO 2+90	0.24	0.24	21.33	21.33	21.33
BACK RD					
STA 8+25 TO 11+75	0.31	0.31	27.89	27.89	27.89
US 136 N					
STA 657+50 TO 659+25	0.27	0.27	24.05	24.05	24.05
CH 11 WEST					
STA 10+75 TO 14+00	0.28	0.28	24.83	24.83	24.83
CH 11 EAST					
STA 10+50 TO 25+50	1.72	1.72	154.81	154.81	154.81
<b>TOTAL</b>	<b>31</b>	<b>31</b>	<b>2,800</b>	<b>2,800</b>	<b>2,800</b>

\* NOT INCLUDING TEMPORARY SEEDING, SEE TEMPORARY SEEDING SCHEDULE

TEMPORARY PAVEMENT MARKING - LINE 24"	
LOCATION	FT
STAGE IA - US 24	
RT 70+20	12
LT 79+96	12
STAGE IA - CH 11 W	
LT 10+91	12
STAGE IA - CH 11 E	
LT 10+67	12
STAGE III - US 24	
RT 28+40	12
LT 38+02	12
RT 70+20	12
LT 81+05	12
STAGE III - CH 11 W	
LT 10+80	12
STAGE III - US 136 N	
RT TURN 661+06	23
LT TURN 661+06	14
STAGE V - US 24	
RT 28+40	12
LT 36+10	12
<b>TOTAL</b>	<b>169</b>

THERMOPLASTIC PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
US 24/ US 136 N ISLAND PERIMETER	145
<b>TOTAL</b>	<b>145</b>

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	
LOCATION	SQ FT
US 24/ US 136 N TURN ARROWS	62.4
<b>TOTAL</b>	<b>62</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY