

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MORGAN	19	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* WEST CHAMBERS STREET				
** 03-00118-00-BR				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22
20200100	EARTH EXCAVATION	CU YD	130
20300100	CHANNEL EXCAVATION	CU YD	335
20400800	FURNISHED EXCAVATION	CU YD	180
25000100	SEEDING, CLASS 1	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	22
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22
25100115	MULCH, METHOD 2	ACRE	0.25
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100
28000300	TEMPORARY DITCH CHECKS	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	165
28000500	INLET AND PIPE PROTECTION	EACH	1
28100207	STONE RIPRAP, CLASS A4	TON	265
28200200	FILTER FABRIC	SQ YD	385
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	147
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	26
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	13
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	66
42001300	PROTECTIVE COAT	SQ YD	52
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	268
44000100	PAVEMENT REMOVAL	SQ YD	76
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	79
44000600	SIDEWALK REMOVAL	SQ FT	251
48101200	AGGREGATE SHOULDERS, TYPE B	TON	38
* 50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
* 50105210	REMOVE EXISTING CULVERTS	FOOT	19
50200100	STRUCTURE EXCAVATION	CU YD	135

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
* 50300225	CONCRETE STRUCTURES	CU YD	51.0
* 50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	2248
50800105	REINFORCEMENT BARS	POUND	4720
51201000	FURNISHING METAL PILE SHELLS 12"	FOOT	738
51202600	DRIVING AND FILLING SHELLS	FOOT	738
51203200	TEST PILE METAL SHELLS	EACH	2
* 51204315	CONCRETE ENCASEMENT	CU YD	3.7
51500100	NAME PLATES	EACH	1
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	34
* 56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	250
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	170
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	99
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	87.5
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	3
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	4
* X3550400	BITUMINOUS BASE COURSE, SUPERPAVE, 7"	SQ YD	660
* X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	96
* X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	103
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	36.2
*	STEEL BRIDGE RAIL, TYPE SM (SPECIAL)	FOOT	154

* SEE SPECIAL PROVISIONS

CONSTRUCTION TYPE CODE
X081

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**WEST CHAMBERS STREET
SUMMARY OF QUANTITIES**

SCALE: VERT. _____
HORIZ. _____

DATE _____ DRAWN BY _____
CHECKED BY _____